

# SCIENTIFIC AMERICAN


[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyrighted, 1890, by Munn & Co.]

A WEEKLY JOURNAL OF PRACTICAL INFORMATION, ART, SCIENCE, MECHANICS, CHEMISTRY, AND MANUFACTURES.

Vol. LXII.—No. 4.  
ESTABLISHED 1845.

NEW YORK, JANUARY 25, 1890.

\$3.00 A YEAR.  
WEEKLY.



1, Delivery of sacks and pouches for outgoing mail. 2, Interior of city drops; facing up letters. 3, Carriers' and stamping clerks' table. 4, General view of main office. 5, Amphitheater for distribution of newspapers. 6, Corridor and private letter boxes. 7, Separating newspapers for city delivery. 8, Newspaper and bulk mail chutes. 9, Storage room for empty bags.

THE NEW YORK POST OFFICE.—[See page 55.]



# Scientific American.

ESTABLISHED 1845.

MUNN &amp; CO., Editors and Proprietors.

PUBLISHED WEEKLY AT

No. 361 BROADWAY, NEW YORK.

O. D. MUNN.

A. E. BEACH.

## TERMS FOR THE SCIENTIFIC AMERICAN.

One copy, one year, for the U. S., Canada or Mexico.....\$3 00  
 One copy, six months, for the U. S., Canada or Mexico.....1 50  
 One copy, one year, for any foreign country belonging to Postal Union, 4 00  
 Remit by postal or express money order, or by bank draft or check.  
 MUNN & CO., 361 Broadway, corner of Franklin Street, New York.

## The Scientific American Supplement

is a distinct paper from the SCIENTIFIC AMERICAN. THE SUPPLEMENT is issued weekly. Every number contains 16 octavo pages, uniform in size with SCIENTIFIC AMERICAN. Terms of subscription for SUPPLEMENT, \$5.00 a year, for U. S., Canada or Mexico. \$6.00 a year to foreign countries belonging to the Postal Union. Single copies, 10 cents. Sold by all newsdealers throughout the country. See prospectus last page.  
**Combined Rates.**—The SCIENTIFIC AMERICAN and SUPPLEMENT will be sent for one year, to any address in U. S., Canada or Mexico, on receipt of seven dollars. To foreign countries within Postal Union, nine dollars a year.

## Building Edition.

THE ARCHITECTS AND BUILDERS EDITION OF THE SCIENTIFIC AMERICAN is a large and splendid illustrated periodical, issued monthly, containing floor plans, perspective views, and sheets of constructive details, pertaining to modern architecture. Each number is illustrated with beautiful plates, showing desirable dwellings, public buildings and architectural work in great variety. To builders and all who contemplate building this work is invaluable. Has the largest circulation of any architectural publication in the world.

Single copies 25 cents. By mail, to any part of the United States, Canada or Mexico, \$2.50 a year. To foreign Postal Union countries, \$3.00 a year. Combined rate for BUILDING EDITION with SCIENTIFIC AMERICAN, \$5.00 a year; combined rate for BUILDING EDITION, SCIENTIFIC AMERICAN and SUPPLEMENT, \$8.00 a year. To foreign countries, \$11.50 a year.

## Spanish Edition of the Scientific American.

LA AMERICA CIENTIFICA E INDUSTRIAL (Spanish trade edition of the SCIENTIFIC AMERICAN) is published monthly, uniform in size and typography with the SCIENTIFIC AMERICAN. Every number of *La America* is profusely illustrated. It is the finest scientific, industrial trade paper printed in the Spanish language. It circulates throughout Cuba, the West Indies, Mexico, Central and South America, Spain and Spanish possessions—wherever the Spanish language is spoken. \$3.00 a year, post paid to any part of the world. Single copies 25 cents. See prospectus.

MUNN &amp; CO., Publishers.

The safest way to remit is by postal order, express money order, draft or bank check. Make all remittances payable to order of MUNN & CO.

NEW YORK, SATURDAY, JANUARY 25, 1890.

## Contents.

(Illustrated articles are marked with an asterisk.)

Appliances, railway.....	57	Meter, device for graduating.....	57
Birds, speed and power.....	53	Meter, standard.....	57
Brake, bicycle.....	53	Museum, Hornerman's.....	58
Brake and starter, Boom's.....	52	Northwestern Miller.....	54
Brush, Buckle's.....	51	Notes and queries.....	60
Bullet, photographic.....	53	Notes, photographic.....	51
Bureau, internat., of weights and measures.....	57	Observatory, Harvard College.....	51
Business and personal.....	59	Patent cases, decisions.....	58
Canal, Muscle Shoals.....	50	Pen, fountain, Bray's.....	54
Cotton, spontan. combustion.....	54	Photograph, astronomical.....	52
Dragon, old, formidable.....	56	Post office, New York.....	49, 55
Engine, compound, Clarke's.....	52	Prints, silver, making.....	51
Gas, natural, items.....	52	Propeller, feather blade.....	53
Horses, bleaching.....	53	Pulley, band, saw, Hoffman's.....	54
House, freight, novel.....	56	Pyorrhea alveolaris.....	59
Hydrogen peroxide.....	53	Qualities, acoustic.....	52
Implement, pruning, Bosch's.....	53	Redoubtable, French war ship.....	59
Inventions, index of.....	61	Solution, toning, platina.....	51
Inventions, mechanical.....	60	Steamers, Atlantic, six new.....	51
Inventions, miscellaneous.....	60	Stone, pumice, production.....	59
Joint, rail, Lynd's.....	54	Sulphate, copper, for potatoes.....	51
Lacquer, Japanese.....	58	Telephone, antiquity of.....	59
Lighting, electric, safety in.....	50	Telephone line, Buenos Ayres.....	58
Lock, door, Connor's.....	57	Tramway practice, novel.....	57, 58
Machine, comparing, universal.....	54	Trimmer, corn, Robertson & Holland's.....	52
Machine, letter stamping.....	56	Wax, bottle, for corks.....	51

## TABLE OF CONTENTS OF SCIENTIFIC AMERICAN SUPPLEMENT No. 734.

For the Week Ending January 25, 1890.

Price 10 cents. For sale by all newsdealers.

	PAGE
I. AGRICULTURE AND IRRIGATION.—Agriculture in the Desert.—The creation of new oases in the Saharan desert by the French.—The Qued Rir and its recent developments, with maps. 3 illustrations.....	11731
Imperial Stack Presses.—Apparatus for forming stacks, involving the application of pressure by hand for shaping and packing the same, both in square and circular form.—2 illustrations.....	11724
II. ASTRONOMY.—The Giants of Starry Space.—The relative sizes of stars.—The insignificance of the sun when compared with other stars in space.....	11730
III. CHEMISTRY.—Detecting Silver in Lead.—By ALEXANDER JOHNSTONE, F.G.S.—A very ingenious method of separating qualitatively silver from gold, applicable to blowpipe work and to regular analyses.....	11734
Oil of Maize or Corn.—By CHARLES EDWARD BOWERS, Ph.D.—A very interesting investigation of the oil extracted from Indian corn, its local use in the seed, and its possible and actual uses.....	11734
The Teaching of Science.—How chemistry should be taught to elementary students.—The symmetrical plan detailed by the British Association Committee.....	11723
IV. CIVIL ENGINEERING.—Recent Progress in Sinking Deep Foundations for Engineering Works.—By CHARLES ORMSBY BURGE.—The present aspect of pneumatic submarine constructions, with interesting examples of practice in India, Africa, and elsewhere, including examples of American engineering.....	11719
V. ELECTRICITY.—New Electric Meters.—Some recent electric meters fully described and illustrated, giving examples of different attempts at solving the problem of commercial measurement. 4 illustrations.....	11726
VI. MINING ENGINEERING.—Hydraulic Gold Finder and Irrigator.—A floating boiler and pump installation arranged for drawing water from a river and attacking its banks for the extraction of gold. 1 illustration.....	11725
VII. MISCELLANEOUS.—Cookery for Workingmen's Wives.—By Consul UNDERWOOD.—Continuation of this important paper, treating of bread and cakes and of sick room cookery.....	11732
Raisins.—The influence of the California raisin industry upon the export of raisins from Malaga.....	11732
VIII. NAVAL ENGINEERING.—The Adaptation of the Steam Machinery in Marine Constructions.—By CHARLES E. EMERY.—A Sibley College lecture giving valuable resume of steam engine practice as applied to ships, including the general dimensions of engines, distribution of steam, etc., with reference to recent practice, including the City of Paris and other notable ships.—1 illustration.....	11729
The New Spanish Submarine Torpedo Boat.—An account of the famous submarine boat Peral, with details of the experiments tried at Cadiz.—5 illustrations.....	11719
IX. PHYSICS.—On M. H. HERTZ'S Experiments.—A very interesting lecture on the classic experiments, giving in short and popular terms an account of the last developments.—2 illustrations.....	11727
The Weight of Water.—The last results reached in determining this important datum, the basis of weights and cubic measures in many cases.....	11733
X. SANITARY ENGINEERING.—The Berlin Exhibition of Apparatus and Appliances for the Prevention of Accidents.—By Dr. JULIUS FORTSMAN.—A very interesting and timely paper on this exhibition, describing the more characteristic exhibits, such as dress for working women in factories, apparatus for insuring safety in theaters, and portable hospitals and apparatus for emergency treatment.....	11725
XI. TECHNOLOGY.—Iime Sulphite Fiber Manufacture in the United States.—By Major O. E. MICHAELIS.—A continuation of this most important paper, disclosing the various alloys used in making sulphiting apparatus, with notes on German practice, and the chemistry of the process treated by Mr. Martin L. Griffin, M.A. 11724	

## SAFETY IN ELECTRIC LIGHTING.

In this city the Board of Electric Control has removed from the poles many dangerous electric light wires. The temporary result is to reduce the illumination of a large portion of the city to the weak glimmer of gas lights, but the public is relieved from the daily occurrence of those shocking tragedies by which many lives were lost.

Another source of danger still remains, greater perhaps than that of the old overhead light wires; we allude to the electrical subways. In efforts to effect the removal of the overhead wires, the city authorities constructed beneath the surface of the streets a system of electrical conduits, called subways, designed to receive the electric wires. These subways now run through the principal streets, and so far no mode has been devised for preventing the infiltration within them of the escaping gas from the gas mains. It is well known that ten per cent of the contents of these mains escapes into the adjacent earth. This gas finds its way into the electrical subways, where it accumulates and forms an explosive mixture large in volume, which is ignitable by the smallest electric spark. The result is a frightful explosion, which tears up the pavements, scattering stones and iron in all directions. Four of these explosions lately took place in New York on one of the most crowded streets, Sixth Avenue. Several others have occurred. Fortunately no lives were lost, but the danger to life is very great. The authorities in trying to manage the electric wires have gone from the frying pan into the fire. The subways are a dangerous nuisance, and there can be no safety until a thorough system of ventilation is introduced. For illustrations of the construction of the subways see SCIENTIFIC AMERICAN of April 20, 1889.

In this connection it is interesting to consider what eminent authorities in Europe say about the safety of electric lighting and the modes they regard as the best. Being three thousand miles away, they are probably disinterested, whereas in this country the electric lighting business is chiefly in the hands of the high pressure companies, who claim their plans are perfectly safe, or can be made safe, and yet they are all the time killing people.

Mr. Werner Siemens, of Berlin, who is probably one of the most practically experienced and scientific electricians now living, in a recent interview with a correspondent of the New York World, expressed himself as follows:

"By well constructed underground conduits the danger of electric light wires can be totally abolished if low pressure currents are used, and the dangers resulting from very high pressure can be reduced to a minimum in the same manner. There is no doubt at all that the greatest proportion of such accidents as have happened in New York will cease on the day when the last overhead wire is buried.

"Gas and water pipes," Herr Siemens continued, "can never act as conductors of dangerous electric currents from the underground wires into dwelling-houses. These pipes, if crossed by such a current, would at once divert it into the ground. It is just so with lightning rods, which electricians frequently connect with the water pipes because they make the easiest and most perfect distributors of electricity, diffusing the current over so wide an area as to make it harmless.

"The insulated wires for street lamps should be placed inside of hollow lampposts. For interior lighting (houses, stores, etc.) no high pressure currents should be used unless the construction is such that every possible danger from contact with conductors and lamps is obviated.

"Electric light conductors will never cause fire unless they are carelessly constructed. A well-planned and properly constructed conductor, supplied with the necessary safeguards, is entirely harmless.

"No death caused by contact with electric wires has ever happened here in Berlin. A few accidents by fire have happened in isolated plants, but always because of faulty construction.

"Overhead wires should never have more than 500 volts pressure. Underground conductors, with transformers, no more than 2,000 volts. The transformers and conductors should, however, be tested up to 5,000 volts.

"My system of insulated conductors, protected by lead cover, asphaltum, and sheet iron, has proved successful wherever it has been used—in Berlin, Munich, Rome, Milan, and other Continental cities. Some of these cables have been in use (partly for high pressure and transformers) for six years, and are apparently good for a long time to come. Their exact duration cannot be fixed. Time only can solve that question.

"This system, or a similar one, will overcome all the difficulties you Americans have to contend with. In conclusion, I will say that high pressure should never be used, except where, for pecuniary or technical reasons, it is impossible to introduce low pressure."

The World correspondent then called on Herr Emil Rathenau, who is president of the Berliner Electricitäts Werke, which supplies the Berlin public with electric lights. He had been kept thoroughly posted by a correspondent in New York of what had been

going on in America, and was quite willing to discuss it.

"I have read," he said, "of the numerous accidents in New York, and, in my opinion, your mayor did an excellent thing when he ordered the electric wires overhead to be cut. They should all be placed underground. There is no danger of the currents being carried into the house by gas or water pipes, and thus making mischief. It is absurd. I think the trouble has been caused by the carelessness of the companies. They were probably trying to make money too quickly.

"There are two kinds of accidents which may be caused by electric light wires. The danger to life is one. That we entirely obviate by using only low pressure, no higher than 300 volts, with which we secure an excellent, clear, bright, and steady light. Never a complaint is heard. We have 80,000 lamps in operation now here in Berlin, and we expect to have 160,000 within a year. You see we attain excellent results with this low pressure. We use the Edison lamps, but all the arc lights in Berlin are also fed by our cables. Formerly we used 400 volts for the arc lights, but we find that 300 volts would work as well. A current of that strength is perfectly harmless. You would scarcely feel it. There is absolutely no danger to life. We have 1,500 men in our employ, who all have more or less to do with the wires, but no one in our employ has ever been killed or even injured.

"It is otherwise, however, with the second class of accidents—fires. Low pressure alone will not prevent that danger. But proper construction will. For five years we allowed no one but our own men to put in the plants. With proper care and safeguards there is no danger. Now we allow other contractors to arrange the individual plants, but they must work according to our rules (here Herr Rathenau produced a formidable set of rules, regulating every detail of laying and arranging the wires, insulation, safeguards, etc.) After the work is done it is inspected by one of our experts, and only accepted if properly done. Besides all this precaution, we have everywhere automatic cutoffs, which at once disconnect the current should any wire become overheated. We allow no single wire to carry more than a fixed pressure. We are responsible for all accidents, but we have none. You Americans are the best mechanics in the world, and if you set to work in earnest to perfect your electric light system, no more accidents will happen. It would be folly to discard electric light merely because you have handled it carelessly and burned your fingers.

"We charge for each new lamp (connections and all) placed in a building, 20 marks (\$5); such a lamp will last forever. Then we charge 5 marks (\$1.25) per lamp a year for keeping it in order, and 4 pfennig (1 cent) an hour of actual use for each lamp of sixteen candle power. At these rates we paid a dividend of 8 per cent this year, besides adding greatly to our reserve fund. Commencing January we reduced the rate per hour to 3-60 pfennig (9-10 of a cent) and still expect to make money. Surely your New York companies can do better than that, for we have a strong competitor in the gas works, which sell 1,000 cubic feet for 5 marks, a much lower rate than obtains in New York.

"Our rates for street lighting are somewhat higher. The city pays us 100,000 marks (\$25,000) for the 108 lamps in Unter den Linden and 36,000 marks (\$9,000) for the thirty-six lamps in the Leipziger strasse. But then these are lights of intense power, and we had to erect the lampposts, make connections, and take care of the entire plant. The lights burn every night in the year, moonlight nights not excepted."

It will be seen by the facts given in the above interviews that electric light can be furnished cheaply and without exposing the public or the workmen employed on the wires to any danger. It can only be done by using a lower pressure. It rests with the New York companies to take the proper steps, or, if they should prove obstinate, it remains for the authorities, backed by the people, to bring them to a sense of their duty. Her Rathenau also said, in the course of conversation, that his company owns and runs the electric works of Madrid, Antwerp, Eisenach, and other cities, and that their experience there was the same as in Berlin—no accidents and no trouble.

## The Muscle Shoals Canal.

The obstructions known as the Muscle Shoals, in the Tennessee River, which covered about 23 miles out of the 453 between Chattanooga and Paducah, at its mouth, are at length overcome by means of locks and dams built by the general government, and the river is now open so that boats loaded at New Orleans can at all times proceed to Chattanooga, and most of the time to Knoxville. The distance from Chattanooga to New Orleans is 1,601 miles, as against 2,067 from Pittsburgh and 1,567 from Cincinnati, and it is claimed the coal freights from Chattanooga to New Orleans will be between 80 and 90 cents, as against \$1.05 from Pittsburgh. The improvement of this short piece of the river has been more or less under construction for sixty years.

**Copper Sulphate for Potatoes.**

A. W. Pearson, of Vineland, N. J., writes as follows to *Garden and Forest*: For many years in this region of southern New Jersey every attempt to grow the peachblow potato has been a failure. At about the time the plant is in blossom and the tubers are say one-fourth grown, a deadly blight invades the potato field and sweeps over it like fire. I have had an acre of peachblows showing every sign of thriftiness and giving promise of a heavy crop, and in one week from the time of the appearance of this blight every plant was dead or dying. It is the prevailing opinion here that the peachblow potato is a variety which is "run out," and its culture has been generally abandoned.

Happening to see, last autumn, a few bushels of small peachblow potatoes for sale, I bought them for the purpose of giving them another fair trial under the protection of the Bordeaux mixture. Last June I plowed a clover sod between the tree rows of an orchard, and there planted these potatoes in five equal plats of three rows each, manured in the row with the Mapes potato manure at the rate of half a ton per acre. The plats lay side by side, running north and south. When the plants were a foot high, and before they blossomed, I began to spray some of them with the Bordeaux mixture, and repeated this operation every two or three weeks thereafter until nearly the last of September. The times of treatment were regulated somewhat by the weather and the frequency of heavy rains. At any rate, I aimed to keep leaves and stalks on the sprayed plats pretty thoroughly whitewashed with the copper sulphate solution, so that its presence was always visible all over the plants. Whenever a drenching rain washed off the application it was renewed as soon as possible. I made the treatments with the portable Eureka spraying machine. I thus sprayed plats 1 and 2, left plat 3 (the middle plat) untreated, and sprayed also plats 4 and 5.

About the time the plants blossomed, the middle plat (No. 3) was, as usual, struck by the blight, and in two weeks all of the potato tops on this plat were dead and dry. The plants on the other plats were green and growing as vigorously as could be wished. They remained green and growing until killed by frost in November.

I then dug and weighed separately the total product of each plat. Plat No. 1, sprayed with Bordeaux mixture, yielded 346 pounds of fine, large, marketable potatoes, which were sold as soon as dug for a dollar a bushel. Plat No. 3, not sprayed, yielded only 164 pounds of small-sized tubers, scarcely one of which was marketable.

The diameter of the largest tuber on the untreated plat was three inches. The diameter of the largest on the treated plat was five inches. There is a marked difference in the cooking of potatoes from the unsprayed and from the sprayed plats. Those from the plat not treated are immature and "soggy." Those from the treated plats are mealy and have all the excellence for which the peachblow potato was formerly esteemed.

I have saved ten or fifteen bushels of these peachblows to plant next year, in the confident expectation of a crop of 350 bushels of potatoes per acre. Under the unfavorable conditions in which these experimental plats of potatoes were grown (between rows of trees twenty feet apart and twenty years old), I did not expect a large crop. Yet the yield of the treated plat (No. 1), 346 pounds from 225 hills, is not bad, under the circumstances, being about 125 bushels per acre.

Of the Bordeaux mixture employed, the formula is: Six pounds of pulverized sulphate of copper (blue vitriol), dissolved in four gallons of hot water; four pounds of fresh lime, dissolved in four gallons of cold water; mix the two solutions, and dilute with cold water to make twenty-two gallons of liquid.

I believe, however, that the ammoniacal solution of carbonate of copper will be found as efficient a fungicide as the Bordeaux mixture, and it has the advantage of being more readily prepared and more easily distributed in spray. Its formula is: Carbonate of copper, three ounces; ammonia, one quart; mix. The copper carbonate will dissolve almost at once in the ammonia liquor. Then dilute this mixture with cold water to make twenty-two gallons of liquid.

**Six New Atlantic Steamers.**

There are now six fast steamers building which will press the City of Paris, of the Inman line, very hard in keeping her position as the champion racer of the ocean. The Hamburg American line, whose twin propeller, the Columbia, made a new record of 6 days 18 hours 10 minutes to Southampton on November 14, will have a magnificent new twin screw ship running in May next. She is to be called the Normania, and is now building at the yard of Messrs. John Elder & Co., the constructors of the Etruria and Umbria. The Normania is a little smaller than the City of Paris, being 520 feet long, with 59 feet beam, and 38 feet depth of hold. She will have 16,000 indicated horse power. She will be launched in March next. The keel of her sister ship is being laid by the Vulcan Shipbuilding Company, Stettin. This vessel will not be ready to run until the

spring of 1892. She will be called the Venetia. The French line also has a big twin screw ship on the stocks, which will probably be running next summer. She is called the Touraine, and is to be several thousand tons larger than any of the fine single screw ships of the French line, which hold the record between New York and Havre. The White Star steamship Majestic, a sister ship to the Teutonic, will be ready to do battle with the City of Paris next spring. The Cunard line will also put two twin screw boats in the field to win back the lost laurels of the Etruria. Their names have not been selected. They will be powerful ships, and will take the place of the Servia and the Aurania, which will do duty between Liverpool and Boston.

**Harvard College Astronomical Observatory.**

The annual report of the director, Prof. Edward C. Pickering, presents much interesting information.

A gift of \$50,000 was received last summer from Miss C. W. Bruce, of New York, for the construction of a photographic telescope of novel form, which, if successful, will materially affect the entire plan of work of this observatory.

For the last six years experiments have been in progress on the use of a photographic doublet in the preparation of maps of the stars. The eight inch telescope now in Peru is of this form, and was mounted here in 1885. Since then 4,500 photographs have been taken with it. With an exposure of an hour twice as many stars can be photographed as are visible with a telescope having an aperture of fifteen inches, and as many stars as can be photographed in the same time with a telescope of the usual form having an aperture of thirteen inches. Moreover, with a doublet a portion of the sky covering twenty-five square degrees can be photographed with good definition, while only three or four degrees can be covered equally well with telescopes of the usual form. The time required to photograph the entire sky will be reduced in the same proportion. With a doublet each hemisphere could be covered in one year with eight hundred plates. In 1885 it was proposed to photograph the entire sky with the eight inch telescope, enlarging the plates three times. The results would resemble in scale and size the charts of Peters and Chacornac. The generous aid of Miss Bruce mentioned above will permit this result to be attained in the original photographs, without enlargement. A contract has been made with Messrs. Alvan Clark & Sons for a telescope having an aperture of twenty-four inches and a focal length of eleven feet.

The first research on the spectrum of over ten thousand of the brighter stars is now nearly completed and is partially in print. The photographs required for the second research on the spectrum of the fainter stars are also nearly complete. The eleven inch telescope has been in constant use throughout nearly every clear night in photographing the spectrum of the brighter stars. This work is approaching completion for all stars bright enough to be photographed by means of present appliances, with the large dispersion now employed. By the use of an improved process for staining plates with erythrosin, the yellow and green portions of the spectrum, even of the fainter stars, can be advantageously studied. Numerous experiments have been made with a device for measuring the approach and recession of stars, by means of an achromatic prism in front of the object glass. Several peculiar spectra have been studied, especially that of  $\zeta$  Ursae Majoris. The periodic doubling of its lines seems to be due to the rotation of two components too close to be distinguished by direct observation. The detection of bright lines in one of the stars in the Pleiades suggests a possible explanation of the legend that seven stars were formerly visible in this group.

During last spring an expedition was sent to Peru in charge of Mr. S. I. Bailey, assisted by Mr. M. H. Bailey. A station was selected on a mountain about six thousand feet high and about eight miles from Chosica. All supplies for the station, including water, must be carried by mules for this distance. Two frame buildings covered with paper have been erected, one for an observatory, the other for a dwelling house. Since May 9 the Bache telescope has been kept at work during the whole of every clear night; 1,236 photographs have been obtained. A large number of interesting objects have been detected, among others several stars having bright lines in their spectra. Including the photometric work described below, the amount of material so far collected is unexpectedly large.

An expedition under the direction of Prof. William H. Pickering was sent in November, 1888, to the summit of Wilson's Peak, in the vicinity of Los Angeles. In order that as much useful work as possible might be accomplished, the thirteen inch telescope and the eight inch telescope now in Peru were sent to Willows, California, where the total solar eclipse of January 1, 1889, was successfully observed. Forty-seven photographs were obtained by the party during the three minutes of totality, and the instrumental equipment was much superior to any previously used for such a purpose. It was not until May 11 that the large telescope was successfully mounted on Wilson's Peak, by

Messrs. E. S. King and Robert Black, but since then it has been kept at work throughout every clear night. The number of photographs obtained is 1,155. The objects photographed are selected from a list of 625 double stars, 143 clusters, and other celestial bodies, such as the moon and planets. As these same objects have been repeatedly photographed at Cambridge with the same instrument, an accurate comparison of the atmospheric conditions of the two places may be made. It will of course be impossible to derive a final conclusion until the observations have extended over at least a year, but the evidence already secured shows that in summer results can be obtained at Wilson's Peak which cannot be obtained here. The difference is very pronounced for such objects as the markings on Jupiter. Clusters like that in Hercules are well resolved, so that the individual stars are easily measured, which cannot be done with the best Cambridge photographs. As a test object the sixth star in the trapezium of the Orion nebula is clearly photographed for the first time. A new variable star has been discovered in the midst of the cluster G. C. 3636. A beginning has been made of the measurements of the position and brightness of the double stars, and it is hoped to extend this work to the clusters, and thus furnish an extensive addition to this department of micrometric astronomy.

**PHOTOGRAPHIC NOTES.**

*A Platina Toning Solution for Silver Prints.*—M. Gastine recommends the following:

A.	
Water.....	9½ oz.
Sodium chloride.....	300 grains.
" bitartarate.....	150 grains.

B.	
Water.....	3½ oz.
Bichloride of platine.....	150 grains.

Add 2 drachms of B to A and tone. "It is advisable," said the author, "to eliminate the silver salts from the paper by one or two washings before toning. If bitartarate is not at hand, take five parts of tartaric acid and mix with four and a half parts of carbonate of soda."

*Gelatinous Bottle Wax for Covering Corks.*—In storing volatile liquids which are solvents of resinous material, the ordinary bottle wax in which bottle necks are ordinarily dipped is generally inadmissible, by reason of the solvent action of the liquids upon it. In such cases the following answers admirably, giving a perfect closing; and, moreover, the top is easily pared off with a knife when the bottle is to be opened.

Soft gelatine or good glue.....	3 parts.
Water.....	9 "
Glycerine.....	2 "

Melt the gelatine in the water, and then stir in the glycerine. Any coloring matter can be added, and the necks should be quite free from grease when dipped. A second dip can be given if the first does not give a sufficient thickness. Manufacturers sending out photographic preparations containing volatile liquids should give this preparation a trial. The top can be stamped while soft with a slightly greased metal seal, or, when set, a warm stereotype (slightly oiled) or an India rubber stamp may be used.

*Mr. J. H. Biggs' Method of Making Silver Prints on Rough Drawing Paper.*

**Salting Solution.**

Soft sheet gelatine.....	4 grains.
(about 0.259 gramme)	
Sodium chloride (common salt).....	5 grains.
(about 0.324 gramme)	
Water.....	1 ounce.
(about 28 cubic cents.)	

Soak the gelatine and dissolve in a water bath. Whatman's drawing paper is floated on this and allowed to dry spontaneously.

**Sensitizing Solution.**

Nitrate of silver.....	60 grains.
(about 3.88 grammes)	
Water.....	1 ounce.
(about 28 cubic cents.)	
Ammonia is added, drop by drop, till the precipitate formed is just redissolved.	

Lay the paper on a flat board, the salted side up, and apply the sensitizing solution freely with a Buckle's brush. Pin the paper up by one corner, attaching a fragment of blotting paper to the opposite corner, to prevent the accumulation of solution. When dry, print, tone, and fix as in the case of a print on albumenized paper. Mr. Biggs recommends a carbonate of soda toning bath. For description of the Buckle brush, see next paragraph.

*The Buckle's Brush.*—This useful implement was quite common and well known in the early days of photography, when negative paper processes were much used, and is very useful when it is important to have a clean brush, or rather mop, for every operation. It is made by taking a piece of glass tube, about half an inch in diameter and six or seven inches long, and drawing a tuft of cotton wool partly into one end of it by a thread or a hook of silver wire, an arrangement easily extemporized.—*Photographic Review.*




**AN IMPROVED COMPOUND ENGINE.**

An engine especially designed for use for marine purposes with twin propellers, both shafts thereof being operated by one engine, and also doing away with the ordinary guideways, lessening the cost of construction and diminishing friction, is shown in the accompanying illustration, and has been patented by Mr. James A. Clarke, of Port Moody, British Columbia, Canada. The high and low pressure cylinders are placed vertically one above the other, the exhaust pipe from the high pressure cylinder leading to the steam chest of the low pressure cylinder, while the piston in the upper cylinder is secured on a piston rod extending downward and connected with a piston operating in the lower cylinder, the exhaust pipe from the latter leading to the outside. On the piston rod common to both cylinders is secured a cross-head pivotally connected by two pitmen with opposite crank arms on crank shafts mounted to turn in suitable bearings on the base, which also supports a frame carrying the low pressure cylinder, on top of which is a frame supporting the high pressure cylinder. The valves in the two steam chests are connected with each other by a valve rod connected at its lower end in the usual manner with the reversing link, operated from eccentrics secured on one of the crank shafts. The crank arms stand at angles to each other, so that the crank shafts are turned in opposite directions, and the position of the link is such that it can be readily changed by the reversing lever to simultaneously reverse the motion of the crank shafts. On the crank shafts are also formed two other crank arms pivotally connected by opposite pitmen with a slide mounted in vertical guideways, supported on a frame erected on the base, the motion of the crank shafts causing the vertical sliding motion of the slide traveling loosely in the guideways, and thus serving as a governor, as, in case one of the propellers becomes disabled, the power of the shaft carrying the disabled propeller is directly transferred to the other shaft through the crank arms, pitmen, and slide, and the other propeller is caused to do all the work. In a heavy rolling sea, also, when one of the propellers frequently rises partially out of the water, this means of transferring the power from one shaft to the other prevents the flying around of one propeller and assists the other. All the parts of this engine are within easy reach of the engineer, and there are so few working parts in motion that it is designed to reduce the friction to a minimum, the power of the engine going direct to the cranks. This form of governor can also be attached to any twin propellers without altering the existing engines.


**A BRAKE AND STARTER FOR VEHICLES.**

The accompanying illustration represents a mechanism, patented by Mr. John H. Boom, for storing power during the descent of a vehicle on a down grade, the power to be utilized in propelling the vehicle upon a level or an up grade. Fig. 1 is a vertical transverse section, and Fig. 2 a plan view. A shaft geared to the vehicle axle carries a sprocket wheel and a spur wheel, while a second shaft supports a sprocket wheel and a

**BOOM'S BRAKE AND STARTER FOR VEHICLES.**

gear wheel arranged to engage the wheels of the first shaft, a clutch being mounted upon the second shaft between the sprocket wheel and gear wheel and arranged to turn with the shaft and engage either of the wheels. A spring mechanism is connected by gearing with the second shaft and a clutch lever and brake for controlling the movements of the mechanism. The spring mechanism consists of a shaft on which are mounted two pinions, below which are arranged two cylinders containing springs, to the upper ends of which are secured rack bars adapted to engage the

pinions, the latter, in the regular operation of the device, first engaging one rack bar to compress one spring, and then the other rack bar to compress the other spring, the rack bars being held to retain the springs under compression until it is desired to utilize

**THE CLARKE ENGINE.**

the power thus stored. The clutch upon the second shaft can then be moved to use the power, first of one spring cylinder and then the other, through the spur wheels and gearing, there being also a flywheel in the mechanism. The change from one spring cylinder to the other, both in compressing the springs and in using the power thus accumulated as required, is automatically made, while the flywheel relieves the mechanism of the shock of stopping and starting.

For further information relative to this invention address Messrs. Boom & Loevinger, White Lake, South Dakota.

**A Wonderful Astronomical Photograph.**

At a recent meeting of the Astronomical Society of the Pacific, at the hall of the Academy of Sciences, corner of Dupont and California Streets, San Francisco, the principal paper of the evening was read by E. E. Barnard, Lick Observatory, on some photographs of the Milky Way and other celestial objects that he had made with a large portrait lens of six inches aperture and thirty-one inches focus, strapped to the tube of the six and one-half inch equatorial of the Lick Observatory, the clock work of the instrument being controlled by hand, with the slow motion rods at the eye end. A star was kept bisected by the cross wires in a high power eye piece on the telescope itself. The additional weight of the camera made it necessary constantly to correct the clock throughout the exposures. With this instrument a negative of the Pleiades was made August 23, last year, with an exposure of 1 h. 15 m. This showed the Merope nebula conspicuously, the sharp prong of nebulosity from Electra, and some of the nebulosity about Maia and Alcyone. A negative of the Milky Way (right ascension 17 h. 57 m., declination south 18° 9'), was made July 28, with an exposure of 2 h. 35 m., another in the region about M 11 on August 2, with exposure 2 h. 45 m., and another of the Milky Way (right ascension 17 h. 56 m., declination south 28°), August 1, with an exposure of 3 h. 7 m., and a negative of the great nebula of Andromeda, August 26, with 4 h. 18 m. exposure. The paper was illustrated by lantern slides from these plates projected on a large screen by the aid of oxy-hydrogen light. The nebulosity of the Pleiades was very conspicuous, and the beautiful cloud forms of the Milky Way, with the myriads of stars that they were partly resolved into, were strikingly fine. The slide of the great nebula of Andromeda, when first projected on the screen, had


a mask over it, with a small hole, representing (to scale) the largest field of the great telescope on Mount Hamilton. This was moved about over the slide, showing successive fields of view, upon and around the great nebula, indicating what could be seen at once in the great telescope. The mask was then suddenly removed, and the entire nebula, suspended amid countless stars, flashed into view. The contrast between the limited space representing the field of the great telescope and the sky as shown by the photographic lens was astonishing in the extreme. This slide shows the great rings of nebulosity that were first proved to exist by Mr. Roberts, of England. By carefully counting areas, Mr. Barnard estimated that on the original plate (8x10 inches) there were distinctly visible no less than sixty-four thousand stars. This entire plate had been reduced to a lantern slide which, upon the screen, brought out peculiarities in the arrangements of the stars that were not even suspected in the original plate. On all these plates the star images were perfectly round.

**On Determining Acoustic Qualities.**

Why is it that our men of science, with all their marvelous achievements in various fields, says the *Real Estate Record and Guide*, have never yet discovered the secret of determining in advance whether the acoustic properties of any building intended to hold large audiences will or will not be good? A recent writer, referring to this matter, says that "we have never discovered the principles applicable to the proportions of a great hall by which the voice is spread and conveyed evenly and in the most perfect manner to all parts. After the building is completed it is, confessedly and notoriously, a matter of accident, and a question to be solved by experiment, whether it is 'good for sound.' Furthermore, when the acoustic quality is not satisfactory, it is often not easy to explain why or to devise means to correct it. Here is a field for discovery that has not yet been worked out, nor do we see any rational attempts to solve the problem. Can it be that it is insoluble? Or is it that the properties of sound are still only imperfectly understood?"

**AN IMPROVED CORN TRIMMER.**

An inexpensive device whereby corn, beans, peas, etc., planted in hills or rows, may be rapidly thinned by removing the surplus stalks, without injury to those left, is shown in the accompanying engraving, and has been patented by Messrs. Dudley B. Robertson and James T. Holland, of Perryville, Ky. Figs. 1 and 3 show the device in different positions in use, Fig. 2 being another view, in perspective. Two standards, having handles on their upper ends, are adapted to slide, one

**ROBERTSON & HOLLAND'S CORN TRIMMER.**

upon the other, and at the lower end of one standard are guard plates, offset to afford clearance for a thinning fork, the lower ends of the guard plates having cutting edges, to facilitate their ready insertion into the soil. Between the guard plates is pivoted a thinning fork, its tines being spaced and attached to a head block, links pivotally connecting the outer end of the head block with the lower end of the sliding standard. There is a foot rest at the side of one of the guard plates to aid in the insertion of the thinner by bearing the foot thereon, when the parts are in the position shown in Fig. 1; the handle on the other standard is then drawn up, rocking the fork as the tines are elevated, as shown in Fig. 3.


For further information relative to this invention address Mr. James T. Holland, Perryville, Ky.

An agreement without consideration is void; a note made on Sunday is void; contracts made on Sunday cannot be enforced.



## AN IMPROVED PRUNING IMPLEMENT.

An implement adapted for pruning trees irrespective of their height, and for dressing the wounds caused by pruning or trimming, so that danger of bleeding is avoided, is illustrated herewith, and has been patented by Mr. Andreas Bosch, of Prairie du Chien, Wis. The invention covers improvements in the construction of



BOSCH'S PRUNING IMPLEMENT.

an implement formerly patented by the same inventor. In Fig. 1 the implement is shown with the saw in position to saw downward from the upper side of the limb, and with the waxing and shearing and planing attachments in position, Fig. 4 showing further how the saw can be set in an angular position. Fig. 2 shows the device without the saw and waxer and with a different shearing attachment, for trimming away small limbs, to facilitate the operation of which there is a hand cord, while Fig. 3 shows a combined chisel and scraper, for use when it is desired to scrape the tree, and clear away the loose bark and insect nests. The pole to which the attachments are secured is sectional, a short metallic tube with split ends receiving the ends of the pole sections, there being bands around each end of the tube, and set screws for fastening them, whereby the pole may be lengthened as desired. The attachment for planing off the stumps of limbs severed by the saw consists of a blade-carrying disk mounted on a drum within which there is a coiled spring, a strap or cord extending downward from the drum, by means of which the disk may be rotated. The wax can is pivotally mounted, a lamp being placed beneath it for warming the wax, the can being tilted to pour wax on the brush for application as desired by means of a downwardly extending cord. The brush is so supported that a rotary reciprocating motion may be imparted to it.

## The Bleaching of Horses.

A curious statement comes from Arkansas concerning a gang of horse thieves, who had for their chief assistant a young woman—a bleached blonde—with the nickname of Sorrel Sue. She was given this name because she always appeared in public riding a sorrel horse. Her excellent horsemanship and her dashing manner brought her many admirers. The shooting affair which forces her into notice was an ordinary case of plain jealousy. Two of her admirers, both members of the gang, fought for her favor. One was killed, and the survivor was severely wounded. A surgeon was sent for. He mistook the direction and walked into the cabin occupied by "Sorrel Sue." Before he could be hustled out, he saw certain things which aroused his suspicions. These he reported to the sheriff, who with a posse managed to surround the den of the horse thieves, capturing Sue and two of her gang. The sheriff, though pleased with the capture, was more than elated at the discovery of the peculiar method of disguising the stolen animals adopted by the gang. He found that Sue had applied the means of bleaching her own hair to that of the horses.

When the posse entered, they found a horse enveloped in a jacket made out of rubber coats, being treated to a sulphur vapor bath.


The appliances were very ingenious, and worked very well. A black or bay horse would be stolen and run into the bleachery. After its color was changed and its tail and mane trimmed, the disguise became so pronounced that without any great risk the animal could be taken in daylight through the very district from which it had been stolen. It was Sue's business not only to superintend the bleaching, but also to ride the animal out of the country.

## Hydrogen Peroxide.

It has been known for a considerable time that when zinc amalgam and water were shaken with air, hydrogen peroxide was found in the solution in small quantities. The greater part formed was however employed in oxidizing the zinc. It has been found that if some substance be present which is capable of combining with the hydrogen peroxide as it is formed, the yield is greatly increased. A patent has recently been granted in Germany (D. P. 48,542) for a process founded on these observations. A fluid amalgam, containing not more than 1 part of zinc or cadmium to 1,000 of mercury, is shaken with milk of lime and air. If a little potash is present, the reaction is accelerated. The hydrogen peroxide combines with the lime, forming calcium peroxide, which is precipitated. The mixed precipitate, containing calcium zinc oxide and calcium peroxide, is treated with an acid which will form insoluble salts with the two metals, while the hydrogen peroxide goes into solution.

## THE FEATHER BLADE ELLIPTIC PROPELLER.

This is a mechanical movement which applies to the propulsion of vessels. The path of the paddle is an ellipse, whose longest diameter is horizontal, so that the paddle or propeller is carried through a certain arc of greater or less magnitude, according to the dimensions of the parts. The longest movement of the paddle is when it is immersed, and the paddle being vertical, there is no splash, slip, or loss of propulsive effect arising from the oblique action. Greater speed can be obtained than by any other form of propeller, and a greater saving of power. The movement can be placed at the side, stern, or center of vessel. Sportsmen will find it of great value running up narrow streams where the common oar could not be used. The foot movement would be of great use for ladies, especially those unable to use the oar. It is claimed that there is a gain of 25 per cent over any other means of propelling on the water. The movements can be made of wood or steel. The propeller can be run by the hand, foot, or by steam power. Designed by George U. Tibbles, Jersey City, N. J.



THE FEATHER BLADE ELLIPTIC PROPELLER, FOR TEAM OR HAND POWER.

## AN IMPROVED BICYCLE BRAKE SHOE.

The soft rubber tire of a bicycle wheel, especially where the rubber is not of the best quality, after a certain amount of use loses its circular form, and, as the brakes heretofore in use have been adapted to take a full hold only when the tire is circular in cross-section, the rider has by no means as full a control of his machine, by means of the brake, when the tire becomes worn. It is to obviate this difficulty that the brake herewith illustrated has been devised and patented by Mr. John J. Astor, Jr., of No. 123 West Twenty-sixth Street, New York City. The brake shoe is made of spring metal, and, as shown in the small view, is slotted longitudinally, so as to cause it to adapt itself to the periphery of the tire without regard to the cross-sectional shape of the latter, and adapt itself with equal advantage to either a new or a worn tire. One or more slots are used as may be required, to enable the brake shoe to fit the tire as perfectly as possible. Its form is such that it can be readily shaped by a drop press or some analogous means, the outer edges of the shoe and



ASTOR'S BICYCLE BRAKE.

the edges of the slits being rounded to prevent the shoe from injuring the rubber tire. The shoe is pivoted to the fork which supports the wheel, and is connected with the brake lever by a rod in the usual way. The several divisions of a shoe thus formed act independently of each other, each division effecting its due proportion of friction, thereby reaching the whole of the tire surface for the frictional bearing upon which the shoe acts.


## The Buenos Ayres-Montevideo Telephone Line.

The trunk line connecting Buenos Ayres and Montevideo was opened with considerable ceremony on October 26. This line, which is 186 miles long, is worked on the Van Rysselberghe system. The work of construction was entrusted by a private company to M. C. Laborde, and the Felten Guillaume cables and bronze wires were supplied by Messrs. W. F. Dennis & Co., of Billiter Street. The line is carried on posts along either side of the River Plate from Buenos Ayres and Montevideo respectively to the points where the river is crossed. The connection here is established by means of submarine cables, which cross the river at a breadth of 28 miles. In the vicinity of Montevideo the bronze wire spans a distance of 460 yards across the river Santa Lucia, by means of poles 108 feet in height. The charges for the use of the telephone are worthy of notice. During the busiest part of the day they are as follows: For five minutes' use \$5, for five to ten minutes' use \$12.50, for ten to fifteen minutes' use \$25. The line has so far given satisfaction both as regards articulation and loudness.

RIFLE bullets are now photographed in their course by means of the electric spark. The camera is taken into a dark room, which the bullet is caused to traverse. As it passes the camera it is made to interrupt an electric circuit and produce a spark, which illuminates it for an instant and enables the impression to be taken. The wave of condensation in the air before the bullet and the rarefaction behind it are visible in the photograph, and can be studied by experts, thus enabling the form of ball or rifle which minimizes the resistance of the air to be selected.

## AN IMPROVED FOUNTAIN PEN.

A pen in which the pen staff or holder is provided with a compressible air bulb for controlling the supply and flow of the ink is shown in the accompanying illustration, and has been patented by Mr. John D. Bray, of Grand Seminary, Montreal, Canada. Fig. 1 is a full view of the pen and holder, Fig. 2 being a sectional view of its forward portion, and Fig. 3 showing a slightly modified construction. The rear end part of the tubular pen-holding section is fitted to slide closely within the forward end portion of the ink reservoir, and this section has entered in it from its rear a short tube, of soft rubber or other elastic material, projecting slightly beyond the back edge of the pen-




BRAY'S FOUNTAIN PEN.

holding section. The latter is also closely fitted with a section and feeding tube, terminating in front in a curved nose piece, with contracted opening, for supplying the pen with ink. The tube entering the rear end of the pen-holding section forms a valve seat for a stationary valve attached to a rod extending centrally backward. A flexible air bulb is arranged in the rear of the ink reservoir, and connected therewith by a filling piece having an air duct through it. This filling piece and the closing piece at the rear end of the air bulb are connected by the backward extension of the valve rod. In the whole construction, including the valve and adjustable pen-holding section, screw-threaded connections and flexible washers are dispensed with. When writing, the flow of ink from the reservoir to the pen is first adjusted by drawing slightly outward the pen-holding section, to open the valve, and afterward by the writer exerting a more or less slight pressure with his thumb and forefinger upon the bulb. After finishing writing, the pen-holding section is moved backward again within the reservoir, to close the valve, and a cap, held on the outer end of the pen-staff, is placed over the forward end of the pen-holding section, when the pen may be safely carried in any position in the pocket.

## AN IMPROVED BAND SAW PULLEY.

A pulley for band saws, whereby an equal tension will be obtained upon the front and back edge of the saw when passing over the pulley, thus obviating the necessity of hammering or rolling the saw in the middle to make the tension of both edges equal, as has heretofore been done, forms the subject of an accompanying illustration, Fig. 1 showing the saw in position on such pulley, of which Fig. 2 is a front elevation. It is a patented invention of Mr. Jacob R. Hoffman, of Charleston, West Va. The pulley is provided with a rectangular peripheral groove at one side of its center, where-



HOFFMAN'S BAND SAW PULLEY.

by the teeth of the saw will be permitted to project beyond the pulley. The depth and width of the recess or groove will be varied according to the size of the pulley and the width of the saw. A saw intended for use in connection with this pulley should be made perfectly straight, and the pulley is designed to insure its remaining in this condition until broken or worn out.

## "The Northwestern Miller."

One of the most beautiful specimens of the typographic art is the holiday number of our valued cotemporary the *Northwestern Miller*, published at Minneapolis, Minn. The specimen referred to contains 128 pages about the same in size as the *SCIENTIFIC AMERICAN*. A large number of elegant and original engravings are presented, among them portraits of the officers of the National Millers' Association, enterprising and vigorous looking men, officers of British trade associations, etc. Several plates in colors of prominent milling establishments are given. Some two hundred and fifty letters are printed from millers in all parts of the country, giving their several views upon the condition, prospects and wants of the trade. The general literary contents are excellent. We congratulate the *Miller* upon its success and prosperity, of which this superb issue is a substantial evidence.

## Spontaneous Combustion of Cotton.

The Boston Manufacturers' Mutual Fire Insurance Co. warn their customers by special circular of new sources of danger of fire from cotton bales impregnated with cottonseed oil, as follows:

Since the introduction of cottonseed oil and its transmission in casks and barrels from one part of the country to another, a new danger has arisen to cotton in transportation, as cotton fibers saturated with this oil are very liable to spontaneous combustion. It may be that the more frequent fires in large cotton warehouses of the South and in cotton ships can be accounted for in this way. Up to this time the mutual insurance companies have been subjected to but one loss in a cotton storehouse which could be attributed to this cause. This season, however, an instance of saturated cotton bales has been discovered in one of our principal mills. Two bales have been received, one of which was saturated to the extent of 256 lb.; the other to the extent of 175 lb. They were fortunately discovered to be in this condition, and a claim for damages has been made upon the transportation companies. A sample of the cotton has been examined at the Institute of Technology, and tested in our spontaneous combustion oven. It ignited at moderate heat in the way in which fibrous substances ignite when saturated with a drying or quickly oxidizing oil. The oil pressed out from this small sample has been subjected to qualitative tests, which prove it to be cottonseed oil. We therefore warn all our members who represent cotton mills that it would be prudent to have their cotton carefully examined for oil, bale by bale, before putting it into the warehouse.

## Natural Gas Items.

According to the *Pittsburg Dispatch* there is still an overwhelming supply of natural gas at some of the wells, however much others have failed.

The *Dispatch* says: Park Brothers were lately obliged to shut down three of their Murrys ville gas wells, owing to the pressure being greater than the pipes can carry. This company has a 20 in. diameter main running from the Murrys ville gas fields; yet so strong and so plentiful is the gas that they assert they can supply not only their own great works, but also the sixteen other large mills which take gas from them throughout the winter with the decreased number of wells.

The pressure at the Homestead reducing station is 500 pounds to the inch. This gives them more gas than they can possibly use. The outlook for the winter for natural gas is as bright as the consumers want, they say. The same inconveniences that were experienced last year by limited supplies, stoppage of work, and in many cases causing hardship and giving limited supplies of bread, are not likely to transpire this winter, according to present indications.

Messrs. Chalmers & Taylor, of Tarentum, Pa., have struck a huge spouter about three miles east from that place. The size of the new well was a surprise, and experts who have examined, agree that the sand is the same as the Murrys ville sand, showing plausibly that a belt connects this territory with the Murrys ville field.


## Speed and Power of Birds.

In an article in the *Forum* Prof. R. H. Thurston says: The vulture is said to fly, at times, at the rate of above 100 miles an hour; the wild goose and the swallow, in their migrations, make 90 miles an hour; and the carrier pigeon has certainly flown long distances at rates of speed ranging from 60 up to 80 miles an hour, and for many hours together. The common crow ordinarily lounges across country at the rate of 25 miles an hour, the speed of a railway train. Professor Langley finds that the power exerted by the eagle in full flight is but a fraction of one horse power. Mr. Chanute computes the power exerted by a pigeon flying 2,200 feet per minute, 25 miles an hour nearly, at  $\frac{1}{16}$  of a horse power per pound, or  $9\frac{1}{2}$  horse power for a flying machine of equally good form, weighing one ton, at 25 miles an hour, or about 50 horse power per ton weight at 50 miles. Mr. Wenham, a member of the British Aeronautical Society, finds, in the pelican, an expenditure of  $\frac{1}{11}$  horse power by 21 lb. of bird, and this is one horse power to 231 lb., or about a horse

power for the weight of a man, allowing ample margin for surplus power. The birds are found to have a surplus lifting power of about one-half. Professor Langley has purchased recently for the Smithsonian Institution the prize steam engine of the Aeronautical Society of 1868, which, with car and screws, weighs only 16 lb., and but 13 without these essentials. To the engineer these facts certainly look encouraging.

## AN IMPROVED RAIL JOINT.

A rail joint designed to insure the rigid support of the abutting ends of the rails joined, and which can be rolled from iron or steel, to form a joint which is strong, durable, and inexpensive, is illustrated here-




LYND'S RAIL JOINT.

with, and has been patented by Mr. Ives Lynd, of 372 Congress Street, Troy, N. Y. Fig. 1 is a perspective view, showing the joint applied, and Fig. 2 is cross section. The joint is made in two sections, each of which is shaped to receive one-half of the base of a rail, and to fit against the rail web and the underside of the rail tread. These sections each have downwardly extending vertical flanges, below the base of the rail between the ties, the flange of one section having a groove, and that of the other a flange adapted to enter the groove, to hold the parts against vertical displacement. These vertical flanges are preferably formed after the sections have been rolled and cut to proper length, thus giving a broad tie-bearing at each end of either section, with recesses to receive the spikes. A joint thus formed constitutes a bridge and vise, preventing the depression of the end of one rail below that of the other, whereby pounding is avoided and a very strong joint is made.

## AN IMPROVED DOOR LOCK.

A lock for stable doors, etc., in which the parts are so arranged that the door will latch upon closing, and the latch will be locked and held against displacement, is illustrated herewith, and has been patented by Mr. John Connor, P. O. box 56, Whitestone, Queens Co., N. Y. Fig. 1 shows the parts as they appear when the door is open, the catch arm pivotally mounted on the door to the left being guided by a strap, and having a catch hook on its outer end, while its inner end is carried downward and connected to a short arm that is rigidly mounted on a key shaft, which extends outward through an escutcheon secured to the outer face of the door. Upon the other door is a keeper adapted to engage the catch hook, and above the keeper is a gravity hook, rigidly connected to a key shaft, an arm with lateral projection holding the gravity hook in the position shown in Fig. 1, and so that the catch hook in entering the keeper will carry the gravity hook forward to lock the door, as shown in Fig. 2. A stop limits the inward movement of the catch hook, so that



CONNOR'S DOOR LOCK.

it will rest practically within the edge of the door when the latter is open, and a button on the other door is adapted to prevent the operation of the gravity hook to lock the doors when it is desired to close without locking them. A key is used for each door, one to raise the gravity locking hook and the other to raise the catch arm to the positions shown in Fig. 1.



## THE NEW YORK POST OFFICE.

In the days of its Dutch occupancy, when the city of New York was termed New Amsterdam, there was no post office. Foreign letters were delivered personally by the agents of ships and by the officers, sailors, and passengers. Unclaimed letters were left in the hands of some private citizen until called for. As the volume of the business increased, a system of voluntary distribution from the taverns was developed, and the so-called "coffee house delivery" was maintained for over one hundred years.

When the English obtained possession of the quiet old city they left matters as they were for some years, but in 1686 an official order was issued that ship letters must be delivered at the custom house, and in 1692 a post office was established, the city then having a population of not far from 6,000 inhabitants.

In 1710 a "chief letter office" was established, and arrangements were made for the delivery of the Boston mail twice a month. On May 4, 1732, the post office was removed to Broadway, opposite Beaver Street, according to an advertisement in the *New York Gazette* of May 3, signed by "Richard Nichol, Esq., P. M." In 1753 Dr. Franklin was appointed Postmaster-General. Up to this time the coffee house delivery was still in existence, and was eventually considered an injury to the revenues of the regular service. Alexander Colden was postmaster of New York until the breaking out of the revolution. For the period of the war the records are missing, but in 1785 William Bedlow held the office, and was succeeded in 1786 by Sebastian Bauman. In the first year of his incumbency the income of the office was \$2,789.84.

A little over one hundred years ago, during Mr. Bauman's incumbency, the post office department, substantially as at present constituted, was established with seventy-five post offices and 1,875 miles of post roads. Josias Ten Eyck succeeded Mr. Bauman, holding the New York office for the year 1803, and was followed by General Theodorus Bailey, who retained the position for nearly twenty-five years, dying September 4, 1828. He moved the office to No. 29 William Street, corner of Garden Street, now Exchange Place. The next move, in 1825, was to Exchange Place, and two years later it was moved to the Merchants' Exchange on Wall Street, between William and Pearl Streets. In 1835 the building was burned in the great fire, and the post office was moved to the rotunda in the City Hall Park. The next change was in 1845, to the Middle Dutch Church, in Nassau Street, extending from Cedar Street to Liberty Street. Thence it was moved in August, 1875, to the present building, erected for the purpose by the federal government.

The building even now affords insufficient accommodation for the operations of the office. It contains too many columns, which are found to interfere with the work of transportation of heavy matter, etc., and before many years some relief will be necessary. A part of the building is occupied by federal court rooms and offices, which eventually may have to be established elsewhere.

The New York office is now under the management of Mr. Cornelius Van Cott, New York postmaster, and represents the highest grade of efficiency in its many departments. Our thanks are due to him and to Mr. J. Gayler, assistant postmaster, for courtesies received. Mr. Gayler is one of the oldest employes, having been in the service for thirty-five years, representing the best principles of true civil service.

The United States Post Office Department may be considered as executing its work in two general divisions, one the railway post office and the other the stationary post offices. The work of the entire department is executed in large and small post offices throughout the country and in railroad cars, its operations ramifying all over the land. To acquire any conception of its processes it must be remembered that one division assists the other to the utmost of its power, each playing into the other's hands.

We illustrate in the present issue the work of the New York City Post Office. The working divisions of the office are as follows: The executive division; first division, financial accounts; second division, mailing and distribution; third division, city delivery; fourth division, registry; and fifth division, money order. In the city, besides the central office, there are eighteen branch stations tributary to it, besides twenty sub-stations at which mail matter is received but not delivered. The branch stations both deliver and collect letters.

Mail matter reaches the New York office through several channels, in some cases with canceled, in other cases with uncanceled stamps. The mail with uncanceled stamps comes to the office in three ways. A part reaches it in bulk from large mailing firms, publication offices, etc. This is delivered on Mail Street, at the north side of the building. Large scales are provided on the platform for weighing it, and it is discharged through chutes, shown in Fig. 8, to the basement. A second source is the letter and package drops in the main corridors of the building, shown in Fig. 6. Another source is lamp-post boxes, whence it is taken by collectors attached to the office.

The first operation the letters have to undergo is termed "facing up;" this means arranging them with their addressed sides all in the same direction and right side up. As fast as the letters fall into the post office drops the clerks in charge thereof perform this work, one of whom thus engaged is shown in Fig. 2. He is a veteran of the war, and has but one arm, yet is found very efficient. As the collectors bring in their collections they also face them up and divide them into two general divisions. One includes letters for city delivery, the other includes out-going domestic and foreign letters. For this work long tables are provided, along one side of which the collectors arrange themselves for facing up and separating their letters, while along the other side are stamping clerks. Both carriers and clerks engaged in these operations are shown in Fig. 3. As fast as the letters are faced up by the carriers they are placed on shelves over the center of the table, within easy reach of the stamping clerk. The letters from the post office drops, already faced up, are handed also to these stamping clerks.

The stamp with which the letters are marked is a double one, containing a canceling device as well as one for post-marking the date and hour. By means of these stamps at one blow two impressions are produced upon the letter, one "killing," as it is called, the stamp, the other giving the time of its deposit. The letters, when being stamped, are placed upon a thick sheet of India rubber. For "killing" the stamps on circulars, newspapers, and packages a special kind of stamp, made of printer's roller composition, without date is used. The time in the letter stamps is changed every half hour by a special clerk who goes the rounds periodically making the change, and, by registering impressions in a book properly divided, keeping a record of changes made. This precaution is taken in order that no possible doubt may exist as to the time at which a letter reaches the post office—and is found particularly useful in cases where negligent messengers have failed to mail promptly letters intrusted to them for that purpose.

The separation of letters received at the New York post office drops is effected, to a certain extent, by the public, who mail them in outgoing domestic, New York City, and foreign countries delivery drops. This corresponds to the first separation made by the collectors.

Letters from other post offices, from branch stations in the city, and from all parts of the world are received with stamps already killed. The date of receipt at New York is stamped upon this class of mail upon the backs. It is termed backstamping.

Upon the main floor in the central office, shown in Fig. 4, are situated a number of tables, from which rise up cases of pigeon holes, each pigeon hole labeled. These are called the separation and distribution tables. Most of these are used for dividing the mail addressed to different parts of the United States and Canada. The first operation is termed separation. There are 75 separation tables, all duplicates of each other, each provided with 90 pigeon holes. The titles of the pigeon holes may be classified in three divisions. The first division includes boxes devoted to a special post office; there are comparatively few. There are ten in the State of New York, three in Pennsylvania, three in Ohio, and so on. The letters placed in these pigeon holes are tied up in bundles and receive no further distribution within the office. The second division includes letters for (a) New York State in general; (b) New Jersey; (c) Pennsylvania; (d) Maine, Massachusetts, Vermont; (e) Connecticut, Rhode Island, New Hampshire, and Canada; (f) Ohio, Indiana, Illinois, Tennessee, Virginia, Texas. All of those mentioned under the second division have to be redistributed in the office. The third division includes remaining States of the Union, and is distributed by the railway post office, after separation on these tables. Five distribution tables receive the second of the divisions designated above from the separation tables. One table is devoted to New York, another to New Jersey, another to Pennsylvania, another to the Eastern States and Canada, and one to the South and Western States, as just specified. Here the letters are still further distributed. Some are placed in boxes, labeled with the names of post offices, to which they go directly. Other boxes are marked with the name of the place followed by the letters "D and D." In these are placed letters intended for direct mailing to that post office, as well as to be distributed therefrom as a local center. A third and very numerous class are marked with the names of railroads, and are distributed from the cars to post office stations on the line of the roads by the railway post office clerks.

On the New York State table 392 of these distributions are made, and on the Pennsylvania and the New England and Canadian tables respectively 224, for New Jersey there are 126, and for the Southwest 72 distributions. Were the clerks simply required to refer the numerous post offices each to the box including it, the feat would be a considerable one, but in addition to this, changes are continually being made, owing to new railroad arrangements, which bring post offices into other boxes, and the clerk has to keep accurate watch of all such changes.

Probably the most complicated department is the New York City distribution. These letters have been separated from the general mail partly by the public mailing them in designated boxes in the post office, partly by the collectors on reaching the office, and the remainder at the 75 separation tables. At the New York City tables pigeon holes are provided open at front and rear. They are arranged and marked to correspond to the carriers' routes supplied from this office and partly to the branch stations. For these the street address is the guide. The distributing clerk must at once refer this address to the proper office in whose district the street is included, or to the carrier's route on which it lies, and throw the letter into its proper box. In some cases the odd and even numbers on a street will fall to different divisions. At the same time the clerk has to watch for all names of holders of lock boxes. These, even if directed to street addresses, go to the box belonging to their receiver. The clerk therefore has to know the name of every box holder in the city, of whom at present there are 3,000.

The mail for foreign countries is distributed on the same general lines by being thrown into proper pigeon holes. In this department there are 14 distribution tables, each having 29 boxes.

The weight of letters passing through the post office is watched. Those that seem too heavy are weighed, in order that unpaid postage may be collected upon them. All such go to the mail inspection and rating department, falling under the first division.

The letters leave the office in pouches after separation and distribution for all districts except the carrier district of the office. They are removed from the pigeon holes, are tied in bundles, and each bundle is labeled with the name of the pigeon hole from which its contents is removed. They have next to be "pouched." For this purpose a large semicircular table is provided with a range of large sized pigeon holes whose floors are inclined downward in the rear. These are marked with the names of railroads, cities, etc. The packages of letters are thrown dexterously into the proper compartments, whose labeling does not correspond necessarily with that upon the packages. At the back of these inclined pigeon holes sacks may be attached by hooks to receive the bundles as fast as thrown in, or the pigeon holes may be closed at the back and their contents removed from time to time. Both systems are employed. The letters go out in these pouches, some to post offices, and some to be opened on the trains and sorted and separated and distributed along the route by the railway post office employees. For city branch offices the pouching is done in simple frames supporting the bags by the mouth as shown in Fig. 7.

To the mailing of newspapers a special department, occupying most of the basement of the building, is devoted. Here the papers and circulars are received in bulk in sacks, which come down inclined chutes from Mail Street, as shown in Fig. 8. The work done here in the separation and distribution compares closely with what is done on the floor above. There are ten separation tables, each with sixty-four divisions or boxes. Five distribution tables are supplied from a limited number of the boxes of the separation tables. There is also one table specially provided for news dealers' packages. The work at a newspaper separation table is illustrated in Fig. 5. As an example of the work done in this department it may be stated that on the New York table there are 576 distributions effected, on the New England table 144 distributions, and for the other three tables from 125 to 150. The third and fourth class matter handled in this department is stamped with a special stamp. Matter sent out from 1 A. M. to 10 A. M. is stamped with a figure 1, from 10 A. M. to 7 P. M. with a figure 2, and from 3 P. M. to 1 A. M. with the figure 3. It is placed on elevators, shown in Fig. 1, and delivered to the mail wagons on Mail Street, north of the building. As the elevator rises and descends it opens and closes automatically a safety door covering the orifice.

In the basement storage for sacks and pouches is provided, as shown in Fig. 9, where they are stored away, labels cut off, and whence they are taken as required. The repairs of sacks and pouches is all executed in Washington.

Forbidden articles fall into two classes—those prohibited by the Postal Union and those by the United States laws. A large quantity of matter is held back as unmailable every year, and the sender notified.

A number of letters with undecipherable or meaningless addresses are received. We give some sample addresses: "Your friend, Claus S. Anderson. P. S. I think I will go to bed. North America." "Shipped Knocked Down. Can be set up by any cabinet maker. New York, Mexico." "A Happy New Year. Thomas Sounel, Cuba." "Mr. Brooklyn President St., New York, United States." The first three represent a very numerous class written from circulars or the endings of letters by those ignorant of the language. If undecipherable they are sent to Washington, and occasionally some are interpreted there.

Some statistics of an approximate year's business will be of interest. Such would include about 216,

000,000 letters, postal cards, and newspapers delivered by carriers, 350,000,000 collected in the city from all sources, 34,000,000 letters forwarded to foreign countries, and over 25,000,000 received from the same. Over half a million of letters are misdirected annually, and of these about 86 per cent are forwarded to their correct destination. The dead letter office at Washington, D. C., receives about one million pieces of mail matter. In a working day, on the average in round numbers, 620,000 letters, weighing 16,000 pounds, are disposed of, in addition to 10,000 sacks of second, third, and fourth class matter. The whole represents 500,000 pounds. The carriers dispose daily of about 8,000 pounds of letters and postal cards. In the year 1889, 200,000,000 pounds of mail were handled in the office. The registered letter department forwarded during 1889 nearly three millions of dollars as gold coin in bulk.

#### NEW LETTER STAMPING MACHINE.

The Hey and Dolphin letter stamping machine is now in full operation in the New York post office. It was put there on trial, seven months ago, by authority of the Postmaster-General. The post office officials here are greatly pleased with it, and Postmaster Van Cott has made a very favorable report of its merits to the Washington authorities.

The machine combines the merits of great speed, effective cancellation, uniform and legible post-marking, and an accurate registry of the number of letters and postal cards operated upon. It is claimed that it will cancel, postmark, count and stack the letters and postal cards at the rate of 30,000 per hour. On November 2, it canceled, postmarked, counted, and stacked 187,980 letters in the course of twelve hours, and it has disposed of 3,000 postal cards in 4 minutes and 50 seconds. It has canceled, postmarked, counted, and stacked 24,000 postal cards within an hour. In two hours and two minutes it canceled, postmarked, counted and stacked 46,480 letters and postal cards, of which 21,000 were letters. Of course this record would have reached higher figures but for the idle intervals which occurred to the machine owing to the failure of the supply of letters.

It is this great capacity for speed that gives to the machine its principal value.

The work of canceling and postmarking letters as done by the old fashioned hand stamp is the chief hinderance to a quick and satisfactory postal service in cities. It sometimes happens that letters and postal cards are deposited in the post office in such great quantities just before the closing of the mail that the clerks are unable to cancel and postmark them in time, and consequently a portion of them must necessarily be detained over until a later mail than the one for which they were posted. Fast mail trains and faithful letter carriers are of no avail for letters detained over because insufficient time has been allowed the post office officials to cancel and postmark them.

The government has been long in need of machinery having great speed for doing this work, and the importance to the public of its introduction at this time cannot be overestimated. By placing the necessary number of machines in each post office the officials will be given absolute control over the quantity of work to be done in a given time, and no letter need be detained for a later mail than the one for which it was posted.


The machine is compact, and condenses its numerous functions and great capacity within very limited dimensions. It comprises a receptacle or hopper, a combined feed and separator, a counter, a printing device, and a stacker.

The operations are wholly automatic. Letters of indiscriminate sizes are placed in the receptacle, and are immediately carried forward to the feed and separator, which feed the letters forward with great rapidity, while preventing the passage of more than one letter at a time.

The letters are placed upon their edges in a species of horizontal hopper, whose under surface is formed by

an endless belt continually tending to draw the letters on. A curved wall deflects them, one a little in advance of the other. They first pass between two feed rolls, carried by vertical spindles, actuated by the driving pulleys, E and F. These pulleys are connected by an endless belt, and one is much larger than the other. This introduces the feature of differential feeding which distinguishes the machine. The roller actuated by the small pulley, F, travels at comparatively high speed in the positive direction, tending to feed the letters forward. The roller actuated by the large pulley, E, rotates in the negative direction, tending to push the envelopes back. The distance apart and pressure exerted by these rollers upon the envelopes between them is adjustable, and all the letters, except one or two, are held back by the differential or negative roller.

In this way the first separation is effected, and two, or at the most three, letters go forward. Another set of differential feeding rolls have next to be passed, which, however, are set much closer to each other. They work on the same principle. The negative rollers are seen at D D, while the driving pulleys with connecting belt are shown upon the top of the frame. These only permit one letter to go through, the rollers,



NEW LETTER STAMPING MACHINE IN USE AT THE NEW YORK POST OFFICE.

D D, holding back any other. Under the action of two positive feed rolls, one of which is shown at B, the letters are fed forward. An ink font, A, and inking rollers, C C, are seen in the front of the machine. Back of these is a feed roller. Working in unison with it, and practically forming a continuation downward of this roller, is a rotating die. The roller, B, acts as a pressure roller, forcing the letter against this rotating die, which cancels the stamp by horizontal lines which extend across its face, and next imprints the date upon the face of the stamp. Trip mechanism is provided, actuated by each letter as it comes forward, by which the die is released from a detent and is clutched to the roller alluded to. It thus rotates with it, and produces the desired imprint upon the envelope. As the letter passes out, the clutch is released, leaving the die loose, and at the same time a stop mechanism is operated, locking the die in a position so that it cannot print. The next envelope that comes along releases the stop, throws on the clutch, so that the die rotates sufficiently to produce its imprint upon the envelope, and is immediately unclutched and locked. The envelopes then pass on to a stacking table, where they drop down before fingers carried by a rotating shaft that continually feed them forward against a board placed at any position desired. A register, H, indicates the number of letters which have been canceled, and is one of the most convenient accessories of the machine. The date and hour in the die are changed by hand.

The machine is driven by a one-quarter horse power electric motor, but can be run by foot power like a printing press. One very valuable feature of the machine is the clearness with which the date is printed upon the envelope. The hand stamp imprint inevitably lacks clearness, but in the machine we are describing the impression is produced with the distinctness of printing. The clerk in attendance watches for envelopes which have the stamp upon the wrong corner, or that have a number of stamps on them, and by feeding them upon other than the top edge secures the canceling of the stamps. The feed rollers are held to their places by elastic bearings, and elastic coiled spring belts are used for driving them. Thus the rollers can be pulled apart to a considerable extent, and there is no danger of the attendant getting his fingers caught or being injured in any way.

#### A Formidable Old Dragon.

In a paper read last November, before the National Academy of Sciences, Prof. O. C. Marsh describes the skull of the gigantic *Ceratopsidae*, the remains of which are found in the Rocky Mountains.

The geological horizon of these strange reptiles is a distinct one in the upper Cretaceous, and has now been traced nearly eight hundred miles along the eastern flank of the Rocky Mountains. It is marked almost everywhere by remains of these reptiles, and hence the strata containing them may be called the *Ceratops* beds.

The skull of *Triceratops*, the best known genus of the family, has many remarkable features. First of all, its size, in the largest individuals, exceeds that of any land animal, living or extinct, hitherto discovered, and is only surpassed by that of some of the Cetaceans. The skull, the type of the species, is that of a comparatively young animal, but is about six feet in length. The type of *Triceratops horridus* was fully adult, and probably an old individual. The skull, when complete, must have been over eight feet in length. Two other skulls, both nearly perfect, now under examination by the writer, fully equal in bulk the two already described, and other similar specimens from the same horizon maintain equal average dimensions.

Another striking feature in the skull of this genus is its armature. This consisted of a sharp cutting beak in front, a strong horn on the nose, a pair of very large pointed horns on the top of the head, and a row of sharp projections around the margin of the posterior crest. All these had a horny covering of great strength and power. For offense or defense, they formed together an armor for the head as complete as any known. This armature dominated the skull, and in a great measure determined its form and structure.

The skull itself is wedge-shaped in form, especially when seen from above. The facial portion is very narrow, and much prolonged in front. In the frontal region, the skull is massive, and greatly strengthened to support the large and lofty horn cores which formed the central feature of the armature. The huge, expanded parietal crest, which overshadowed the back of the skull and neck, was evidently of secondary growth, a practical necessity for the attachment of the powerful ligaments and muscles that supported the head.

THE *Northwestern Railroader* learns that a large railroad company has the plans for a three-story freight house in Chicago, nearly 300 feet long, and will run cars on a track and by hydraulic lifts raise it to the second story and then run a second series of cars on second track and raise that to second story. Terminal ground is certainly getting valuable, and railroad managers will watch with interest to see three trains being loaded or unloaded at one time into a freight house from the same side. If the plan proves feasible a great saving of ground rent will be rendered to all railroads terminating in large cities.



## LABORS OF THE INTERNATIONAL BUREAU OF WEIGHTS AND MEASURES.

The first meeting of the General Meter Conference was held at the pavilion of Breteuil (St. Cloud Park), from the 24th to the 28th of September, 1889. The mission of this conference was to sanction the labors of the International Bureau of Weights and Measures, and to receive the metrical prototypes designed for the subscribing States of the meter convention. It consisted of the International Committee of Weights and Measures, of the French section of the Meter Commission, and of the diplomatic or scientific delegates of the States represented in the reunions of 1872. The president of the Academy of Sciences was the president of it *de jure*. The Minister of Foreign Affairs, desirous of showing the great interest that the government took in this conference, opened the first session himself.

We shall say but little of the conference itself, of which we might give a pretty accurate idea by merely reproducing the speeches that were delivered. It was at the second session that the prototypes received their official sanction, and were distributed by lot among all the States. The international meter and kilogramme, so exact copies of those of the Archives that it is impossible to detect the direction of their errors, were placed in a strong box, situated in a deep cellar closed by three locks, whose keys were respectively in the hands of the director of the bureau, of the president of the committee, and of the guardian-general of the Archives. The extraction of these standards by an officer of the International Bureau was, therefore, subordinated to the authorization of the International Committee and the French government. It could take place only in the presence of the depositaries of the various keys. These precautions, which at first sight seem to be a little excessive, were necessary in order to give all the States the absolute guarantee that the fundamental standards of the metrical system should run no danger of being injured by ill-disposed or careless persons.

As we have said, the mission of the conference was to sanction the labors relative to the new prototypes of the metric system. We propose to pass these various labors rapidly in review.

It will be remembered that the Meter Commission, renouncing the primitive and theoretic definition of standards, decided simply to copy the meter and kilogramme of the Archives in their present state. The problem was, therefore, reduced to the making of these copies, then to the getting up of immutable standards for the States, and to the determining of their exact value.




Fig. 4.—UNIVERSAL COMPARING MACHINE.

The selection of the metal was a subject of profound discussion. The material for the meters and kilogrammes had to be very hard and unchangeable with time, not attackable by atmospheric agents and by ordinary chemical agents, and very refractory, in order




Fig. 1.—STANDARD METER. Fig. 2.—FLEXION OF THE RULES. Fig. 3.—DEVICE FOR GRADUATING THE METER.

to resist even the temperatures that might accidentally occur in the fire of a laboratory.

The important labors of H. Sainte-Claire Deville led to the adoption of an alloy of platinum and iridium

(the latter in the proportion of 10 per cent). This metal is extremely hard; its resistance verges on that of steel, and its temperature of fusion is that of dazzling white (according to Mr. Violle, 1,775° for platinum and 1,950° for iridium).

The metal necessary for the construction of the metrical standards was ordered from Messrs. Johnson, Matthey & Co., of London, who, after long researches, succeeded in purifying it. The difficulties of separating the last traces of rhodium and iron from the iridium were, says Mr. Matthey, almost insurmountable. It took no less than eleven consecutive analyses, the result of which was not declared satisfactory till October 18, 1885.


The hardness of the metal, which is an important quality for the construction of standards, rendered the manufacture of them particularly difficult; it was necessary, from the lessons of experience, to modify the

tools employed for planing metals. Finally, after numerous experiments, the first rule was delivered in April, 1886.

The rules have the form shown in Fig. 1. This form, which is odd, at first sight, has been so calculated by Mr. Tresca that the distance of the divisions limiting the meter and engraved upon the surface, A, are independent of the support of the rule. Fig. 2, in which the flexions are purposely exaggerated, shows that the upper surface of a rule elongates or contracts according as it is supported at the center or at the ends. The median line, called the surface of neutral fibers, remains sensibly invariable. The X-shaped standard has been so calculated, moreover, as to effect as much saving as possible in the very costly material.

Most of the old standards of precision are very delicate and can be handled only with the greatest care, if it be desired to prevent permanent distortions; the new ones, on the contrary, are exceedingly strong, and are capable of undergoing shocks without danger. Accurate experiments have shown that a weight of forty kilogrammes can be suspended from the middle of an X-shaped meter without permanently modifying it.

The rules, delivered in a crude state by Messrs. Johnson, Matthey & Co., were finished and cut to the length of 102 centimeters by Messrs. Brunner Bros., of Paris. Then they were polished and engraved at the Conservatoire des Arts et Metiers. A beginning was made by polishing a space near each extremity, and then the rule was placed in a horizontal comparing apparatus, where it received the two lines defining the meter, and each accompanied with two other lines at half a millimeter from the central line. Thus there was obtained, at the same time with the metric standard, the micro-metric standard, under the form of two millimeters.



A NOVELTY IN TRAMWAY PRACTICE.—[See page 58.]

A brief description of this mode of engraving will doubtless interest some of our readers.

Upon a board, B (Fig. 3), is placed the model rule, I, and the rule to be engraved, H. The apparatus having been adjusted, the first line of the rule, I, is brought under the microscope, M. Then, by a proper movement of the diamond graver, a line is marked upon the rule, H. The board is then shifted parallel with the axis of the rules, until the second line of the rule occupies in the microscope exactly the position in which the first was found; then a new line is engraved upon H, and so on. The entire engraving is done without the operator seeing his work; it is not until he has finished it that he can examine it. The least defect necessitates the entire work being begun over again, for, in view of the precision that it is necessary to expect, it is impossible to mend an interrupted division. This difficult work, performed by Mr. Gustave Tresca, has succeeded in an unexpected manner; one of the first meters engraved, compared with the standards at the International Bureau, served as a type for the rest of the operations. Now, among the thirty meters thus engraved, there is none whose equation reaches  $3\mu$  (three thousandths of a millimeter), and the mean of all is exactly equal to the International meter; whence we conclude that there was no systematic error in the instruments.

We shall not expatiate upon the manufacture and adjusting of the kilogrammes, which presented difficulties of another nature, and not so great. The iridium-platinum cylinders that served for this were strongly compressed in a powerful apparatus in order that all the small internal cavities might be crushed. The movement of the density shows the continuity and, within certain limits, the purity of the metal.

While awaiting the delivery of the standards, the Bureau occupied itself with the elaboration and improvements of the methods of comparison. The first apparatus, which were quite imperfect, were partially replaced with those which have already been described; and others completed the collection.

A long series of comparisons had put the Bureau in possession of provisional standards of the meter and kilogramme, whose equations with respect to the standards of the archives were exactly known. But it was still necessary to determine a certain number of copies for the labors of the Bureau, to measure their expansion, and to get up standards of the subdivisions of the meter and kilogramme. On this subject a few words of explanation may not prove amiss. To speak only of the measurements of length (the same reasonings and nearly the same processes are applicable to the masses), we may say that although there exists in the world one meter exact by definition, it cannot be pretended that we have a perfectly accurate single decimeter, centimeter, or millimeter. Remaining within the limits of practice, we can assert that, in a well divided meter, there are but very few millimeters whose error is less than the limit of the errors of observation.

If we desire to find the error of a millimeter, we begin by comparing the divided meter with the meter exact by definition. Afterward, on comparing the decimeters with each other, we ascertain the excess of each of them over their mean, and, consequently, the error of each separate decimeter. Afterward, by an analogous process, we pass from decimeters to centimeters, and from centimeters to millimeters. This operation, which we are describing in a few words, takes nearly a year of assiduous work. It may be done by means of an instrument called a universal comparing machine—called universal because it permits of measuring all the lengths between certain limits, while most comparing apparatus are designed solely for measuring definite lengths, generally one meter or several meters.

The universal comparing machine (Fig. 4) consists essentially of two microscopes, M, movable upon a very massive cast iron bridge, A, supported by stone pillars, P. The rules are placed upon two supports, B, capable of being moved in all directions.

The tests can be made by different processes. The simplest consists in fixing the two microscopes upon the bridge at an invariable distance, say of 1-10 m., for example, and in making all the decimeters of the rule pass successively in their field. The two microscopes thus form an optical compass by means of which each decimeter is measured separately.

We shall speak further along of the various other labors undertaken by the Bureau. For the present, we wish to terminate what concerns the study of the prototype standards designed for the subscribing States. Here again we shall speak only of the meters, of which thirty have been delivered. For the kilogrammes, forty in number, the principle of the methods of comparison was exactly the same.

The standards were designated by numbers, arranged upon horizontal and vertical lines. Each standard was then compared with all those of the same horizontal line and of the same vertical column. Each comparison of two meters was made four times, by alternately placing one end of each of the rules to the right and left of the observer.

The series of comparisons of the meters numbered

784, to which must be added nearly 400 series for the measurements of the expansions. As each series comprised 6 measurements of one rule and 5 of the other, we reach the very respectable number of about 13,000 measurements. This required an uninterrupted labor of two years.

The measurements were made independently by several observers and by means of various apparatus. Their variations therefore give a good criterion for the accuracy of the same. They also indicate the limit that it is now possible to obtain. A profound study leads to the admission that the errors of the equations scarcely exceed  $0.2\mu$  (two ten-thousandths of a millimeter) for the rules, and are certainly less than  $0.01$  mg., for the kilogrammes. The accuracy of the weighings, greater than one hundred thousandth, or to a magnitude corresponding to 10 centimeters upon the terrestrial quadrant, is the greatest of all that can be obtained in physical measurements.—*La Nature*.

#### A NOVELTY IN TRAMWAY PRACTICE.

We illustrate a novelty in tramway practice, taken from the railroad operated in the beautiful town of Ontario, San Bernardino County, Cal. The railway passes through the middle of Euclid Avenue, a broad and beautiful street, bordered with orange and lemon trees. The avenue is some  $6\frac{1}{2}$  miles in length, with heavy grades as it approaches the hills.

The car is drawn up hill and over the levels by a pair of mules, but in going down grades the mules ride and the car moves by gravity, as shown in our engraving. A platform with folding sides is provided, which is supported near one end upon a pair of wheels. The opposite end of the platform is supported on the car. When the mules are the tractive power the sides of the platform are folded down and the whole rolls back under the bottom of the car, where it remains and is drawn along the track with the car. The wheels on which the platform is carried are of small diameter, and near them is a brake bearing directly on the rail when applied by the conductor.

On down grades the platform or truck is drawn out from beneath the car, the sides are raised, and the guard rails, etc., are adjusted. The mules are driven upon the platform, the gates are closed, and all is ready for the descent. The mules quietly stand, well fenced in, while the car rapidly runs down the grade.

We are indebted to Mr. E. P. Slater, of Ontario, Cal., for photographs from which our illustration has been prepared.

#### Horniman's Museum.

We have just had the privilege of being conducted by Mr. Horniman over his unique collection of curiosities. Mr. Horniman's museum is probably the most complete, if not the largest, of any private museum in the country, and is the result of thirty years collecting at considerable expense and diligence by the owner.

But by far the most extensive and complete section of the museum is devoted to specimens of beetles and butterflies (Coleoptera and Lepidoptera), of which there are over 12,000 specimens, in 500 drawers, and South America is in this section exhaustively illustrated.

South America is particularly celebrated, not only for the abundance but also for the surpassing beauty of its insect fauna, among which may be mentioned the huge silk-producing moths of Brazil, belonging to the genus *Attacus* (allied to the Indian Atlas moth) and *Polythysania*; the hummingbird moths, *Calliomena*, *Enyo*, etc., also the true hawk moths, *Chorocampa*, *Pachylia*, *Philampelas*, and other genera common in Panama and Colombia. Castina endesmia from Chili, and others belonging to the same genus from Brazil, Colombia, and the upper Amazon, are almost unique among moths by having clubbed antennæ or horns, which is generally considered to be the distinguishing appendage of a butterfly, but this is an exception to the rule.

In the *Thrysana* (night-flying moths) is found one whose spread of wing is nearly eleven inches. This is found in Brazil. The beetles from Brazil alone are legion, from the lovely longicorn or long-horned beetles, *Psalidognathus*, whose beauty can only be compared to monstrous jewels, to the little curious *Cosmisoma*, with tufted legs and horns. Brazil also produces the wonderful beetle, *Dynastor*, *Hercules* (an old world name for a new world insect), the back or thorax of which in the males is lengthened out into a horn or spear about four inches long, underneath which is another attached to the head and movable, the two forming a weapon resembling the claw of a lobster. Then there are the Diamond beetles, so called from their exceeding brilliancy; in fact, Brazil, Nicaragua, Panama, Chili, and the other countries in South America all combine to produce such numbers of species as are found in no other part of the globe. The butterflies are as numerous. H. W. Bates, in his "Naturalist on the Amazons"—a charmingly written account of a charming country—speaking of Para, gives the number of species of butterflies that may be found within an hour's walk of that place as 700. The total number found in the British Islands does not exceed 66, and in the whole of Europe less than 400. Beautiful

Heliconias throng the paths in the woods, while the gorgeous metallic blue *Morphas* soar aloft, scores of feet high, in the bright sunshine, the reflections of whose iridescent wings may be seen afar off—some say a mile—and the hummingbirds add to this scene of enchantment.

The museum is open to the public, on Wednesday and Saturday afternoons, by cards of admission to be had from Mr. E. D. Watkins, the genial curator, 100 London Road, Forest Hill; and Mr. Horniman permits also natural science classes, or parties interested in the works of nature and art, to go over the museum under the charge of the curator. It is, however, necessary to arrange beforehand, in order that a convenient time may be appointed for the visit. South American visitors, and those from India, would be peculiarly interested in the collection, as the fauna of those continents is so well represented.—*Chemical Trade Journal*.

#### DECISIONS RELATING TO PATENT CASES.

##### Supreme Court of the United States.

WATSON vs. THE CINCINNATI, INDIANAPOLIS, ST. LOUIS & CHICAGO RAILWAY COMPANY.

Letters Patent No. 203,226, granted to Chauncey R. Watson, April 30, 1878, for improvement in grain car doors, *Held* to be void for want of patentable novelty if construed to consist of the combination, in a freight car having an outside rigid door, of an inner flexible sliding grain door.

Where the complainant's door was carried on rods and staples and the defendant's door moved in grooves, *Held* that even if there was no material difference between the doors of complainant and defendant, respectively, there was no infringement, for complainant had in effect disclaimed defendant's door.

A patentee will not be permitted to say that certain specified elements of his combination claim are not essential to the combination.

An alleged combination which consists in a mere aggregation of parts, each to perform its separate and independent function substantially in the same manner as before combination with the other and without contributing to a new and combined result, is not patentable.

#### Trade Marks.

##### Superior Court of Cincinnati—State of Ohio.

HOEB *et al.* vs. BISHOP *et al.*

A small metallic frame containing a portrait fastened to a pin, so as to be used as a personal ornament, does not constitute a valid trade mark when so attached to and sold with a cigar as to be readily detached and used separately in the manner indicated.

An article having a distinct commercial value of its own cannot be made a trade mark for another article by being attached to and sold with it.

Where it is charged that the defendant has imitated the packages of the plaintiff for the purpose of imposing the goods of the former upon the public as those of the latter, not only must the fact of imitation be shown, but it must also appear that the imitation was made with intent to impose upon the public as aforesaid, and such intention may be presumed from the fact of imitation, but the presumption is not conclusive, and may be overcome by facts showing that the imitation was for other and innocent purposes.

#### Japanese Lacquer.

Mr. Romyn Hitchcock described recently to the Washington Chemical Society the manner in which Japanese lacquer and the beautiful Wakasa ware are prepared. Lacquer is obtained from a tree, *Rhus Vernicifera*, which grows throughout the main island of Japan, but is best around Kioto. The juice, from which lacquer is obtained, exudes from horizontal cuts in the bark, and is collected from May to October. It exudes slowly, and is collected with a pointed instrument like a spoon, and transferred to a wooden receptacle. A dozen trees are cut in several places in rapid succession, and the juice collected from time to time. During the season each tree is visited about twenty times. As the sap first exudes it is a grayish white, thick or viscous fluid, which quickly turns to yellow, and afterward to black, when it is in contact with the air. It is strained through a cotton cloth to free it from wood and dirt, being first thoroughly stirred to make it of uniform consistency. A portion of the raw lacquer, usually about 16 lb., is then poured into a large circular vessel and vigorously stirred with a long-handled implement for five or six hours, while the heat of a small charcoal furnace is ingeniously thrown on the surface to evaporate the water. During the stirring certain ingredients may be added. Thus, iron is added to produce the fine black lacquer. In Tokio, a soluble salt of iron is used for this purpose; in Osaka, a fine iron dust. The lacquer is then poured into a vessel to settle, and is afterward drawn off from the sediment.

THERE is a great increase in the consumption of African teakwood, on account of its property of preserving from rust iron or steel that is in contact with it.



**The Production of Pumice Stone.**

We often hear it remarked, and particularly after an eruption of a volcano, that pumice stone ought then to be plentiful and cheap, as quantities must have been ejected during the volcanic disturbance. As a matter of fact, however, none of the white stone in general use is obtained from active volcanoes. It is true that Vesuvius has ejected pumice stone, for at the time when Pompeii was destroyed large quantities fell over the doomed city, but that pumice appears to have been only of diminutive size, and is gray in color, and of the same inferior character as that found to the north of Naples. It is also probable that volcanoes situate in the southern seas emit pumice, for accounts are published now and again of vessels sailing through quantities stretching for miles upon the surface of the water. This, presumably, is similar to that taken from the sea near the Italian shores. It is small in size, and in the form of pebbles, having been rounded by the action of the water.

As already stated, we are not indebted to ejections from volcanoes for our supply of stone. It is to actual deposits of the article discovered in one or two quar-

Some years ago it was almost the general custom to send the stone loose in the vessels to the Leghorn merchants, who sorted and packed it for shipment. This custom, however, has been altered, and by getting the stone sorted at the place of production, far better results have been obtained than formerly. There is no doubt but there is now less good stone to be found than used to be the case. For one ton of good light stone a miner has to have many tons of inferior quality to dispose of, and now that prices have been so interfered with by the operations of the syndicate that has been formed to acquire the working of the principal portion of the mines from the municipality, it has become a question of paying a very high price for stone we could formerly obtain for far less than it now costs.


**THE FRENCH WAR SHIP "REDOUTABLE."**

The "Redoutable," one of the ships in the French squadron of evolution at Toulon, was constructed in 1876. She is built of iron and steel, 318 feet 2 inches long, and with 64 feet 8 inches breadth of beam, having a displacement of 9,200 tons, and drawing 25 feet 6 inches water. Her engines are 6,071 indicated horse

**Pyorrhœa Alveolaris.**

This is an insidious disease which begins by a deposit of tartar upon the necks of the teeth and gradually creeps in, reaches the roots, clinging to the exterior thereof. The teeth become loose, painful, and extraction is often deemed necessary. But some dentists are successful in effecting cures. Some treat the disease by introducing scraping instruments, thereby removing as much of the tartar from the roots as they can; then injecting sulphuric acid or peroxide of hydrogen, followed by alkali and an antiseptic. At a recent meeting of the New Jersey State Dental Society, Dr. James Truman, in the course of some remarks upon the subject, said:

"Does it originate from tartar? Not if I understand it. When you take a patient in hand who states that in the morning when he brushes his teeth the blood will ooze from the gum, you know what the condition is. Here and there a tooth will present a bright red line at the border line of the gum. The moment that it is touched blood will ooze from it, by the disturbance of the capillaries at that point. That is the beginning. And if you take it in hand at that stage, you

**THE FRENCH IRONCLAD "REDOUTABLE."**

ters of the globe, the best of which is at present to be found in the island of Lipari, situate in the Tyrrhenian Sea. The island is of no general interest, and is scarcely visited at all by any but Italians engaged in trading in its productions, such as currants, capers, wine, and pumice. It is mountainous in character, and consists of tuffs and lavas and of highly siliceous volcanic products. The district where the stone is found is called Campo Bianco or Monte Petalo (1,500 feet above the level of the sea). It is an interesting ride there upward from the town. The views obtained of land and sea during the ascent are very fine, and the effect produced by the first sight of the pumice deposit curious, for after riding a considerable distance, partly along precipitous paths, sufficiently dangerous to be interesting, and partly through vineyards and over grassy plains, one almost suddenly comes upon a seemingly snow-clad narrow valley inclosed by hills, also quite white, and the whole glaringly bright on a sunny day, such as can be experienced in this southern latitude. Into these hills workmen are ceaselessly digging deep burrows, working within by candle light. In their excavations they come across many lumps of pumice stone, which are placed in baskets, subsequently being conveyed along the valley to the seashore, where small boats are loaded and sailed to the seaport near by, where the stone is sorted, packed, and shipped to distant parts either *via* Messina or Leghorn.

power, working twin screw propellers, and giving a speed of 14.66 knots an hour. The coal storage is 510 tons, sufficient for steaming 2,800 miles at 10 knots an hour. The hull is protected by a belt of armor plate 14 inches thick, and the central battery has 9 inch plate armor, with 15 inch backing. The guns in the central battery are eight breech-loading 24 ton guns, with caliber of 27 centimeters diameter, rifled; and the barbettes guns are six 3 ton guns of 14 centimeters bore. She carries also twelve machine guns and four torpedo tubes.—*Illustrated London News*.

TELEPHONES and speaking tubes are of greater antiquity than most persons are aware. The speaking tube is a contrivance mentioned in ancient writers, and comes down to us or survives just as candles and oil lamps have not been altogether superseded by gas and electricity. In 1667 Robert Hooke, of London, described how he transmitted sound by means of a wire to considerable distances. Wheatstone described his "telephone" in 1821, and in 1854 Ch. Bourseul said: "Suppose a man speaks near a movable disk, sufficiently pliable to lose none of the vibrations of the voice, that this disk alternately makes and breaks the currents from an electric battery, you may have at any distance another disk which will simultaneously execute the same vibrations. It is certain that in a more or less distant future, speech will be transmitted by electricity."

can stop pyorrhœa alveolaris. It has nothing to do with tartar. It may come from constitutional disturbances; it may come from some form of nephritis or a long siege of sickness. What then follows necessarily after this? Immediately succeeding we have a development of micro-organic life. When you place a rubber dam, or a clamp, or ligatures upon teeth, you produce irritation, and the patient will complain. You take off the instrument, and you allow the patient to go away without any treatment whatever. In forty-eight hours there will be a development of micro-organisms, and pain will result, and irritation at the neck of the tooth, and if it is not stopped at that time, it may go on until this pathological condition which we call pyorrhœa alveolaris appears.

"I hold that no dentist should put a rubber dam in the mouth, or a clamp on the teeth, or do anything of that kind liable to raise inflammation at the necks of the teeth, without applying an antiseptic. For this purpose I know nothing better than sulphate of quinia, mixed into a paste—not because it is the best germicide, but because it is more lasting than other agents."

A PERMANENT and durable joint can, it is said, be made between rough cast iron surfaces by the use of mineral asbestos mixed with sufficient white lead to make a very stiff putty. This will resist any amount of heat, and is unaffected by steam or water.

## RECENTLY PATENTED INVENTIONS.

## Railway Appliances.

**CAR COUPLING.**—John Bender, Marion, Kansas. Combined with the drawhead is a coupling hook pivotally connected thereto, a weight arranged in connection with the hook, a jaw being pivotally connected to the drawhead and a plate mounted within a recess in the jaw, and links by which the jaw and plate are connected, with various other novel features.

## Mechanical.

**NUT LOCK.**—Isaac S. Humbert, Staunton, Va. The bolt has an integral thread and the nut has a transverse groove in its threaded portion, the bottom of the groove being curved, and in connection therewith is used a transversely wedge-shaped and longitudinally curved and tapered key having a hardened or steel body, a soft tip, to adapt it to cut the bolt thread and clasp in the nut groove.

**JOURNAL BOX.**—Ezra L. Post, New York City. This invention covers a bearing provided with a continuous series of anti-friction rolls, a roll-holding attachment, and radial anti-friction rolls, making a bearing designed to operate with a minimum amount of friction, and one in which the parts are so arranged that very little friction will be produced at times when the journal shaft is revolving and the bearing is subjected to side thrust.

**SAW SWAGING MACHINE.**—Henry P. O'Connor and Antoine Leduc, Manistee, Mich. This machine has two side disks and a handle between them, the latter fulcrumed on a shaft secured on a plate, the construction being such that the tooth during swaging is engaged on all four sides, on the top and back by dies, and on its sides by flanges which limit the tooth point to the desired width.

**PUG MILL ELEVATOR.**—James H. Steele, Butte City, Mon. This is an elevator for conveying mud to the mud mill of brick machines, the conveyor slightly compressing the mud as it passes up from the hopper, and clearing the mud of stones and other hard substances.

**CLAMPING DEVICE FOR SAW TABLES.**—Joseph Balsley, Seymour, Ind. This is a clamp designed to be instantly adjusted to any width of lumber, to hold it while being cut by the saw, the slotted saw table having a stationary edge flange, in connection with grooved guideways, a stop with recessed base, a chain, with sprocket wheel, shaft, and hand lever.

**FEED DEVICE FOR ORE FURNACES.**—Albert C. Johnson, Wilmington, Del. The shell of the furnace has openings in its top and a hopper whose openings are out of alignment with those in the top of the shell, there being apertured gates between the shell and the hopper, and means for alternately reciprocating the gates, whereby the ore may be fed regularly to the furnace and the supply cut off as soon as the furnace is stopped.

**DRILLING MACHINE.**—William H. James, Pittston, Pa. This machine has a rectangular frame with an opening in one of its end bars, a sliding crosshead in which is swiveled a socket, an internally threaded guide ring and a threaded feed bar, with means for operating it, and other novel features, the machine being designed for boring out charge holes in rock, etc., while not being heavy or burdensome.

## Miscellaneous.

**POCKET BOOK.**—Isaac Scheuer, New York City. This pocket book has a bag with pivoted jaws and a separate and independent bag suspended from its upper longitudinal edges within the first bag, and having closed ends with folds extending above the points or pivots of the jaws and closing the end spaces between them.

**CARPET FABRIC.**—Joseph Jagger, Ripton, N. Y. This is a new article of manufacture, consisting of a fabric having the usual warp threads binding the filling threads in place, and a third or middle warp thread for binding the filling thread carrying the pile down into place.

**HALTER, YOKE, AND BRIDLE.**—Peter J. Krater, St. Mary's, Mo. This is a combination device of halter and attachments, enabling one device to be used as a substantial halter or as a guard to prevent an animal jumping or breaking a fence or injuring himself thereat, while allowing him to feed and water himself freely from or at the ground, being also adapted for use as an open riding bridle or a blind driving bridle.

**CLOTHES LINE PROP.**—Robert McAlpine, Trenton, N. J. The pole or prop consists of two pieces of wood of suitable length, one section being notched at intervals on one side and the other section being held by clip bands to slip on the notched section, in combination with a spring dog to which is fixed a threaded stud and a nut.

**CLOTHES LINE SUPPORT.**—John B. and Robert Johns, Findlay, Ohio. This support consists of a shank with a head beyond which there is a spiral section, the support to be driven into a post, and obviating all knotting of the line, while providing for the ready taking up of any slack.

**CLOTHES LINE.**—Charles Barlow, Cookshire, Quebec, Canada. This line has a metallic core, with a spirally wound wire covering turning freely on the core, in order to lessen the possibility of the clothes being cut or torn when blown to and fro in the wind.

**CLOTHES PIN.**—Edward M. Watson, Jersey City, N. J. This pin is preferably made of one piece of metal wire, in the form of a head piece with three arms projecting therefrom, so made that it may be used to fasten garments or fabrics to a line without danger of tearing the fabrics in applying it, or by their being blown about by the wind.

**WASHING MACHINE.**—John S. Headen and John T. Boswell, Pleasant Hill, Mo. This invention consists of a fixed corrugated or fluted board and a second corrugated or fluted board adapted to slide on the first one, making an improved washboard which is simple and durable.

**SCOW.**—William Osborn, Duluth, Minn. This scow has compartments communicating with a suction pipe just below compartments in the bottom of the scow, valves connecting the compartments and pipe, which pipe is open at both ends, and communicating at one end with the water below the scow, to provide a simple and cheap way of unloading sand or any substance that will flow with its own gravity.

**STEAM LIQUID HEATER.**—John F. Bradford, Leetonia, Pa. This invention covers an improvement especially intended for use in heating tanning liquors, whereby the degree to which the liquor is heated may be automatically regulated, the highest heat being obtained by subjecting all the coils of the liquor pipe to the live steam, while by permitting the water of condensation to cover the coils to a greater or less extent, the degree of heat is lowered as the quantity of water is increased.

**WAVE MOTOR.**—Robert B. Davy, San Diego, Cal. This invention provides a float or buoy fixed in such a manner as to vibrate on the surface of the water within a limit of ninety degrees, in connection with suitable mechanism to retain the float in position and utilize the vibratory movements to convey a continuous running movement to a drive shaft located on shore.

**PAPER FEEDER.**—George W. Crane and Harry Bradshaw, Topeka, Kansas. Rock shafts are journaled beneath an adjustable paper-carrying table, with a rock shaft above the table from which elastic fingers are suspended, and connections between the shafts, with other novel features, making a device for feeding paper into a ruling machine, a perforator, or any machine to which paper is to be fed one sheet at a time from a pile.

**BREECH LOADING GUN.**—James Jensen, Park Place, Ark. The barrel of this gun has a projection arranged for engagement by a spring bolt, a catch holding the bolt in retracted position, a slide and catch being arranged in connection therewith, a thumb piece being carried by the slide, and a lever connected to the slide and to the bolt, providing for the secure locking of the barrels when moved to firing position, for improving the action of the extractor, etc.

**BOOT OR SHOE VENTILATOR.**—Peter Welander, San Francisco, Cal. This is a short tubular shell of sheet metal having a flange turned over outwardly upon one end, and the opposite end closed by a perforated plate, making a ventilator which may be readily secured in place at any desired point upon a boot or shoe, and set in open or closed position, to afford thorough ventilation of the interior.

**TOE WEIGHT.**—Elwood L. Gregg, Hoxie, Kansas. This weight has a dovetail or undercut groove, which a fastening bolt is formed to fit, having on its rear side a projection arranged to engage a clip, whereby the weight may be securely held to a horseshoe and conveniently applied to and removed therefrom.

**EXTENSIBLE TRETTLE.**—Gustav Bogusch, of Vallecillo, Mexico, and August Zinke, of Llano, Texas, administrators of Robert J. Bogusch, deceased. This trestle has a brace frame with parallel connected end bars having hook-shaped ends with set screws, and other novel features, making a strong and simple construction for a scaffolding for masons, carpenters, etc., which may be readily put together and taken apart.

**BIRD TRAP.**—Benjamin Walton, Compton, Cal. This is a spring trap so constructed that most of its parts may be entirely in the top part of a post or stake, but so arranged that when a crow or hawk or other birds alight on the post a spring-held catch will be released, and arms with serrated teeth will be closed over the top of the post, thus seizing the bird.

**HAY STACKER.**—Daniel H. Talbot, Sioux City, Iowa. This is a machine designed to be ordinarily operated by means of a team attached thereto for stacking hay, ensilage, etc., the machine being portable and capable of automatic elevation as the stack is formed, while it is designed to form a stack with but little manipulation or attendance on the part of the operator.

**CORSET CLASP.**—Frank B. Converse, New York City. This clasp has a catch plate with a slot that is narrow at one end and around the slot a depressed flange, the locking stud having a head rounded underneath and adapted to enter and engage the catch plate, making a clasp which may be readily fastened or unfastened even by a child.

**BOOM BRUSH BRIDLE.**—John B. Butenshon, Portland, Oregon. This bridle consists of an upper and lower wire loop connected together and each having an eye for the passage of the free end of the wire, making a cheap and efficient clamp for holding the brush of a broom in form without stitching.

**WINDOW CLEANER.**—George Pilson, Yonkers, N. Y. This device has a brush head with a bore in alignment with a bore in a hollow handle, a receptacle with a series of apertures being secured to the head, whereby a continuous supply of water may be fed to the cleaning surface of the implement.

**KNIFE CLEANER.**—Joseph Thompson, Decoto, Cal. This is a household implement, designed to be simple and inexpensive, for the cleaning of table knives, the main object being to provide for the yielding support of the polishing material and the delivery of it in such quantities as may be required.

**CHECK CUTTER.**—Leonidas C. Pressley, Brooklyn, N. Y., and William Lombard, Wheatland, Cal. This device has a base plate with a fixed right-angled cutting edge, in combination with a right-angled knife pivoted at the ends of the plate at

diagonally opposite corners, for cutting checks or other billets of various sizes from check books or sheets.

**AERATING MILK.**—Aldis O. Morgan and Jerome B. Gates, Hermon, N. Y. This invention covers an apparatus adapted to be readily fitted to a milk can, whereby a continuous supply of cool air may be passed through the milk for cooling it and driving off noxious volatile matters.

**CABINET FILE.**—John Muhlhauser, Rochester, N. Y. This casing has rigid horizontal panels loosely mounted upon one another in the casing, lugs at their rear ends pivotally connecting the panels with the casing and being vertically movable therein, making a convenient receptacle for sheet music, papers, etc.

**FOLDING BED SCREEN.**—John J. Griffith, San Bernardino, Cal. Combined with a frame having rubber-lined uprights and a folding top, on which a mosquito bar is secured with side flaps, are weighted pockets to hold the mosquito bar in position against the uprights and on the floor, with other novel features, the screen being one which can be readily folded up, and permitting of ready ingress to and egress from the bed.

**SASH BALANCE.**—John S. Headen and Coleman G. Farmer, Pleasant Hill, Mo. This is designed to be a simple, ornamental and reliable device whereby the upper and lower sashes may be arranged to counterbalance each other, and be relatively adjusted in the window frame as desired.

**JUG HANDLE AND STOPPER.**—Simeon L. Bray, Evansville, Ind. This is a combination device, consisting of a stopper having a transverse hole through it, through which passes a handle extending to the sides of the jug, while a bail is connected to the jug and arranged eccentrically in the handle, whereby the mouth of the jug may be closed by turning the bail handle.

## SCIENTIFIC AMERICAN BUILDING EDITION.

## JANUARY NUMBER.—(No. 51.)

## TABLE OF CONTENTS.

1. Elegant plate in colors of the residence of C. F. Callahan, Esq., Buffalo, N. Y. Perspective elevation, floor plans and details.
2. Plate in colors illustrating a cottage on Staten Island, N. Y. Cost three thousand dollars. Floor plans, elevation and sheet of details.
3. Page engraving of a chimney piece by Hugues Lallemant, Museum de Cluny, Paris.
4. Perspective elevation and floor plans of a house at New Rochelle, N. Y. Cost five thousand eight hundred dollars.
5. A residence costing twenty-four hundred dollars, erected on Chester Hill, Mt. Vernon, N. Y. Floor plans and perspective elevation.
6. A dwelling recently erected at Stamford, Conn., at a cost of seven thousand dollars. Plans and perspective.
7. Engraving of a French bay window, constructed in the style of Henry III.
8. United States post office and court house, Lancaster, Pa.
9. A handsome residence at Larchmont Manor, erected at a cost of seven thousand dollars. A. Sargent, architect, New York. Perspective view and floor plans.
10. A cottage recently erected at West New Rochelle, N. Y., at a cost of three thousand eight hundred dollars. G. O. Haur, architect, New Rochelle, N. Y. Floor plans and perspective.
11. A residence at Grand Rapids, Mich. Cost complete, six thousand dollars. Plans and perspective.
12. An attractive dwelling at New Dorp, Staten Island, N. Y., erected at a cost of \$5,000. Plans and perspective.
13. Engraving of the Corbin building, corner John Street and Broadway, New York city, built on a plot of ground 20 feet by 162 feet.
14. A dwelling at Chester Hill, Mt. Vernon, N. Y. Cost complete \$5,800. Perspective elevation and floor plans. Architect H. S. Rapelye, of Mt. Vernon, N. Y.
15. A very attractive dwelling at Ludlow, N. Y., recently completed at a cost of \$4,773 complete. Architect Benj. Silliman, Yonkers, N. Y. Plans and perspective elevation.
16. Miscellaneous Contents: The hornbeam.—The Peerless Brick Co.—The American Institute of Architects.—The Henderson heaters.—Regenerative gas lighting, illustrated.—Filtering and purifying water, illustrated.—Foot power mortising and tenoning, illustrated.—Architectural sheet metal work, with two illustrations.—The Manhattan dumbwaiter.—Hot water heating.—Academy of Architecture and Building.

The Scientific American Architects and Builders Edition is issued monthly. \$2.50 a year. Single copies, 25 cents. Forty large quarto pages, equal to about two hundred ordinary book pages; forming, practically, a large and splendid MAGAZINE OF ARCHITECTURE, richly adorned with elegant plates in colors and with fine engravings, illustrating the most interesting examples of Modern Architectural Construction and allied subjects.

The Fullness, Richness, Cheapness, and Convenience of this work have won for it the LARGEST CIRCULATION of any Architectural publication in the world. Sold by all newsmen.

MUNN & CO., PUBLISHERS,  
361 Broadway, New York.

## Business and Personal.

*The charge for insertion under this head is One Dollar a line for each insertion; about eight words to a line. Advertisements must be received at publication office as early as Thursday morning to appear in next issue.*

All books, app., etc., cheap. School of Electricity, N. Y. For Sale—Patent No. 315,598. Folding bracket seat. When closed resembles handsome raised panel. Perfect for churches and halls. O. E. Briggs, Binghamton, N. Y. Wanted—Volume 19, year 1881, United States Official Patent Gazette. State price to J. W. E., 401 E. Market St., York, Pa.

Salesmen can add to their incomes by selling our goods on commission. Commissions to one salesman, who devoted only one hour daily to our goods, averaged twenty-five dollars per month for past three months. Our goods have been on the market for twenty-one years, are well known, and are first class in every respect. Address "Commission," care Scientific American, New York.

Wanted—Experienced mechanical draughtsman. Address, stating ability and salary, Balto. Sugar Ref. Co., South Baltimore, Md.

We desire to receive communications from those who contemplate patenting any new method or material for the covering of steam pipes, boilers or other heated surfaces, and will pay for valuable suggestions, or unpatented formula, if accepted, tending to improve the products of this class, now on the market. Address, B. C. D., P. O. Box 773, New York City.

Machine tools, catalogue No. 47-B; wood-working machinery, catalogue No. 52-A; steam power, catalogue No. 48. Largest lines offered by any firm in this country. Send for bed-rock prices, stating exactly what you want. S. C. Forsaith Mach. Co., Manchester, N. H.

Best Ice and Refrigerating Machines made by David Boyle, Chicago, Ill. 140 machines in satisfactory use.

Guild & Garrison, Brooklyn, N. Y., manufacture steam pumps, vacuum pumps, vacuum apparatus, air pumps, acid blowers, filter press pumps, etc.

For the latest improved diamond prospecting drills, address the M. C. Bullock Mfg. Co., Chicago, Ill.

Presses & Dies. Ferracute Mach. Co., Bridgeton, N. J.

The Holly Manufacturing Co., of Lockport, N. Y., will send their pamphlet, describing water works machinery, and containing reports of tests, on application. Turck water motors at 12 Cortlandt St., New York.

Screw machines, milling machines, and drill presses. The Garvin Mach. Co., Light and Canal Sts., New York. Billings' Patent Breech-loading Single Barrel Shotgun. Billings & Spencer Co., Hartford, Conn.

The Improved Hydraulic Jacks, Punches, and Tube Expanders. R. Dudgeon, 24 Columbia St., New York.

Friction Clutch Pulleys. The D. Frisbie Co., N. Y. city.

Tight and Slack Barrel Machinery a specialty. John Greenwood & Co., Rochester, N. Y. See illus. adv., p. 173.

Send for new and complete catalogue of Scientific and other Books for sale by Munn & Co., 361 Broadway, New York. Free on application.

## Notes & Queries

## HINTS TO CORRESPONDENTS.

**Names and Address** must accompany all letters, or no attention will be paid thereto. This is for our information, and not for publication. **References** to former articles or answers should give date of paper and page or number of question. **Inquiries** not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and, though we endeavor to reply to all, either by letter or in this department, each must take his turn. **Special Written Information** on matters of personal rather than general interest cannot be expected without remuneration. **Scientific American Supplements** referred to may be had at the office. Price 10 cents each. **Books** referred to promptly supplied on receipt of price. **Minerals** sent for examination should be distinctly marked or labeled.

(1742) A. M. H. asks: Please inform me what will take wood smoke from coach windows. A. Wash with whiting and soap.

(1743) W. G. O. writes: What ingredients are looked for in sanitary water analysis? What are the best and latest books on the subject? A. Chlorine, ammonia, free and albuminoid organic matter, oxygen required to oxidize same, are the principal data sought for. We recommend MacDonald, "Water Analysis," \$2.75; Wanklyn & Franklin, "Water Analysis," \$2; and Austen's "Hand Book for Water Drinkers," 50 cents.

(1744) F. A. B.—The object that you send is a gall, which has been produced upon some plant by the sting of an insect.

(1745) W. S. B. writes: 1. I want to attach leather to tin without having to roughen the tin. What can I use for a cement or glue? A. As a simple preparation use a freshly made solution of gum tragacanth. It should be about as thick as butter. Ordinary glue mixed with tannic acid and at once applied, or a preparation made by soaking shellac in strong ammonia for ten days, may answer your purpose. 2. I have a lot of soluble glass with which I have mixed shellac. What can I add to make it still more adhesive to use as a cement for ordinary purposes? A. You cannot make it satisfactorily adhesive as a cement for general use.

(1746) G. A. O. asks how to construct and connect a spark coil so that with the proper gas fixtures he can light three gas jets, not at the same time, that is, so that one can be lighted without lighting the other two? A. For coil use five pounds No. 18 magnet wire wound around a bundle of iron wires one inch thick and six inches long. From one end of the coil carry three wires, from the other end carry one to the battery, thence three wires, thus making two to each burner. Use a switch or key in each line.



(1747) E. T. asks: What is the form and advantage of a bilge keel as differing from an ordinary keel, applied to a ship? A. Bilge keels, as their name implies, may be only a deep strake along each side of a vessel at the bilge, or at the most prominent point in the curve from the main keel to the water line, for the purpose of preventing excessive rolling in vessels having high centers of gravity. They increase skin friction and have a retarding effect by their curved form of line, otherwise the only advantage is to lessen the draught of the vessel, by dispensing with the center keel. They do not compensate for the loss of leeway in dispensing with the main keel. In fact, we can see no value in bilge keel except to prevent excessive rolling in overbalanced steamers.

(1748) F. K. asks: 1. What causes warm gusts of wind to come when the air is quite cold, and especially in the fall and spring just before a storm? A. In the fall, owing to dry air and rapid radiations, great differences of temperature may occur within a small area. Thus wind may carry warm air to a cool locality very quickly. When such sudden changes occur, the conditions are favorable to disturbances and storms. 2. How long will the common iron road bridge last? A. If taken care of, it will last many years. They have not been in use long enough to determine the factor of endurance. If neglected and left unpainted and unrepaired, they may very quickly go to pieces.

(1749) M. H. D. asks the process of making diamond ink for etching on glass. A. Mix sulphate of baryta with hydrofluoric acid.

(1750) J. J. asks: What cement will set quickest and firmest cast on collodion? A. Use a strong solution of collodion for above purpose.

(1751) J. L. asks: What number of wire is used to wind the magnets of an electric bell such as is commonly used? A. Use No. 24 wire.

(1752) Frank asks: Would you inform me through the columns of your valuable paper how the white ink is made, such as is used on colored paper? A. A solution of oxalic acid may be used on blue paper. Or a body ink may be made by rubbing up Chinese white with gum arabic water.

(1753) H. J. L. asks how to solidify paraffine oil. A. Solution of glue and emulsion of slippery elm bark have both been suggested as materials to mix with oil for producing a species of gelatinizing or solidifying.

(1754) A. V. F. asks: 1. How much hydrogen gas will an ordinary 1 volt average size battery set free in twenty-four hours? A. None on closed circuit, as the voltage is too low to decompose water. 2. Is there any way of electro-plating other articles besides metallic ones? A. Several ways are practiced. The simplest is to thoroughly coat the object with plumbago. A little fine iron powder may, with advantage, be dusted over the object, after applying the plumbago, if it is to be copper-plated.

(1755) A. H. R. asks: 1. How can I magnetize a needle sufficiently strong to use in a galvanometer? A. Rub it a few times, always in one direction, with the same pole of a magnet. 2. What is the best shape to use—round or flat? A. It is immaterial. 3. Will watchspring do? A. Yes. For a description of a home-made and highly sensitive galvanometer we refer you to our SUPPLEMENT, No. 628.

(1756) J. H. F. asks to be referred to paper showing how to make filter for domestic use. A. We refer you to our SUPPLEMENT, No. 451, for descriptions and illustrations of simple and effective home-made filters.

(1757) H. W. K. asks: Is there any chemical that will etch on the polished surface of patent leather? A. No such acid is known. Nitric acid or oil of vitriol would have a slowly corroding effect, but we believe no practical results can be obtained.

(1758) W. A. B. writes: I am building a wooden aquarium, and would be much obliged if you would tell me the best cement to use in putting in the glass and also the best paint to coat the bottom with to make it impervious to water? A. Use a mixture of Burgundy pitch 150 parts, old gutta serena in fine shreds 25 parts, finely powdered pumice stone 75 parts, for cement, and paint bottom with same. It must be applied hot, and a hot iron wire may be used to melt it into crevices, etc.

(1759) F. G. F.—To remove warts apply a solution of chromic acid. It will blacken them, and eventually it is said will remove them. Or touch every day with a stick of lunar caustic, first moistening the wart.

(1760) E. B. and G. F. W.—For a fusible metal resembling silver, the following alloys are more or less available:

	a	b	c	d	e	f	g
Bismuth...	6	6	3	none	none	1	1/2
Zinc...	3	none	none	none	none	none	none
Lead...	13	13	1	3	20	100	4 1/2
Tin...	none	3	1	3	7	4	none
Copper...	none	none	none	none	none	8	1/2
Antimony...	none	none	none	none	none	8	1/2

All are parts by weight. The last two are particularly recommended as imitating silver.

(1761) E. P. is referred to the SCIENTIFIC AMERICAN SUPPLEMENT, Nos. 69, 227, and 265, for notes on celluloid. Pyroxyline, or nitro-cellulose, is ground in water to a pulp. To 2 parts by weight of dry pyroxyline 1 part of finely divided camphor is added. After thorough mixing and kneading together, the mass is placed in moulds, and is heated under pressure to a temperature of 150° to 300° F. for a sufficient time. It is left to cool under pressure in the mould.

(1762) W. I. L. says: You have been publishing very interesting articles on various subjects, but there is one very interesting subject about which I

have never seen anything in your paper, and that subject is Submarine Boats. Will you kindly tell your readers something about this? A. See SCIENTIFIC AMERICAN SUPPLEMENT, Nos. 218 and 320, for illustrated description of submarine torpedo boats, and many others under the head, "Torpedo Boats," in our catalogue. Our literature on this subject is very full in the SUPPLEMENT.

(1763) D. H. D. asks what is used on moulds in casting lead to make casting smooth and bright. A. Moulds for casting lead are made of iron or brass, or else of sand. Pure lead does not run smooth and bright when cast. By adding a little tin, tin and antimony, or tin, antimony and bismuth, a free-running alloy can be made that will make smooth, bright castings.

(1764) J. M. asks: Will you kindly inform me as to the best way of raising water from a rapid river to irrigate level beach land about 20 to 30 feet above the river? A. In a rapid river there is supposed to be fall enough for the use of water wheels and pumps for the purposes of furnishing water for irrigating land. A dam of convenient height, a race for obtaining sufficient fall, a turbine, overshot, or breast wheel, and a pair of plunger pumps, seem all that is necessary for elevating water to moderate heights. In the absence of details as to the situation and facilities for erecting a pumping plant, we cannot be expected to give specific information.

(1765) H. Y. asks how poplar, walnut, and other woods are stained, so as to imitate cedar, in the manufacture of cigar boxes? A. They are veneered. If you will soak a piece of the box in water, the veneer will come off, disclosing the way it is made.

(1766) H. W. asks: 1. What size of wire should be used for a bell, to be operated by one Leclanche cell? A. No. 24. 2. How long should the cores be? A. One and one-half inches. 3. How thick? A. Three-eighths of an inch. 4. Will cast iron do for the cores? A. They should be made of wrought iron. 5. If soft iron is heated and hammered to fit, will it injure the magnetic property? A. The iron should be annealed after working. 6. What should the armature be—steel or soft iron? A. Soft iron. 7. Should the current start from the positive pole, through the electro-magnet, then to the negative, and back to the battery? A. It makes no difference which way the current runs through the magnet. 8. What size should the conducting wire be that runs from the battery? A. No. 18. 9. Will cast iron make as good electro-magnet as malleable iron? A. Soft gray cast iron makes a fair electro-magnet. It is probably better than malleable iron, but is not so good as wrought iron. 10. In what number of your paper are there directions for making induction coil? A. You will find information on the construction of induction coils in SUPPLEMENT, No. 160. 11. How long should the wire be for the bell mentioned in the beginning of the letter? A. The depth of the winding on the bell magnets should be equal to the diameter of the core.

(1767) W. A. M. asks: 1. Is there a writing fluid of any color other than black or red that will stand? A. Yes; you will find many inks described in our SUPPLEMENT, No. 157. 2. Will you kindly give recipes used for preparing inks suitable for use in shading pens? A. Make a solution of gum arabic of sufficient thickness, and color with aniline previously dissolved in a little alcohol.

(1768) Zero asks: 1. What is gum salt? A. Gum salt may be a name for crude rock salt. 2. What is rock alum? A. Alum in large crystals. 3. What is white vinegar? A. Vinegar that is destitute of color, generally supposed to be made from white or colorless wine. 4. There is a spring of magnetic water in Chardon, O. What is the cause of its being magnetized? A. There is no such thing as magnetized water. 5. Where can I procure a catalogue of locomotives? A. You will find many locomotives described in the SCIENTIFIC AMERICAN and SUPPLEMENT. 6. If we had a boiler with 40 lb. steam in it, and should pump in a 100 lb. air pressure, keeping the heat the same, would it condense the steam? A. If the water were kept at the same temperature, the steam would for the most part condense. You must supply page reference for your other query.

(1769) W. P. writes: 1. Could you tell me the composition of a blacking which, when applied to leather, retains its brilliancy for a length of time without a second application? A. See query No. 1704. 2. I have a large quantity of paint scrapings from pots and kegs, etc. How can I reduce them and use them over again for a priming coat? A. Grind them in a paint mill with oil.

(1770) K. McL. says: I have seen it asserted that the Mississippi River runs up hill through its lower course. I have no doubt you are conversant with the statement and the reasons given therefor. At the present I find it very difficult to understand how this can be, since nothing can recede to a position further from the center of the earth than that which it at first occupied without some impulse which totally overcomes the influence of gravity. Now, as is well known, centrifugal force does not decrease the weight of a body to any considerable extent at the equator. Therefore, it appears to me very difficult to comprehend how the Mississippi can run up hill. A. Centrifugal force does decrease the weight of a body at the equator; 195 pounds at the equator is about equal to 194 pounds at the poles, as far as weight is concerned. The earth is nearly an oblate spheroid. The distance from the surface to the center at the equator is about 3,962 miles, while from the surface at the poles to the center is about 3,949 1/2 miles, the polar surfaces being depressed 13 1/2 miles below the surface of a perfect sphere of the diameter of the earth at the equator. A simple computation shows that the mean surface of the earth at New Orleans is nearly 600 feet further from the center of the earth than at Cairo. At the same time the gravity slope of the Mississippi from Cairo to New Orleans, a distance of about 1,000 miles by the way of the river, is about 2-8 inches per mile at mean water, or 233 feet that it runs down hill from Cairo to New Orleans with a gravity datum, but it recedes in so doing 387 feet from the center of the earth, which in one sense may be considered up-hill.

## TO INVENTORS.

An experience of forty years, and the preparation of more than one hundred thousand applications for patents at home and abroad, enable us to understand the laws and practice on both continents, and to possess unequalled facilities for procuring patents everywhere. A synopsis of the patent laws of the United States and all foreign countries may be had on application, and persons contemplating the securing of patents, either at home or abroad, are invited to write to this office for prices, which are low, in accordance with the times and our extensive facilities for conducting the business. Address MUNN & CO., office SCIENTIFIC AMERICAN, 361 Broadway, New York.

## INDEX OF INVENTIONS

For which Letters Patent of the United States were Granted

January 7 1890

AND EACH BEARING THAT DATE.

[See note at end of list about copies of these patents.]

Accordion, J. T. Henderson	419,168
Adding and subtracting machine, J. H. Schnar-	418,930
renberger	418,930
Aging liquors, J. A. H. Hasbrouck	418,792
Agricultural implement, J. Arnold	419,027
Agricultural machines, etc., seat for, C. Benesh	418,677
Air wetting apparatus, A. Petit	418,746
Alarm. See Low water alarm.	
Annunciator, J. Finck	418,968
Anvil mould, T. W. Vane	419,088
Auger, well boring, G. Meader	419,055
Barrel head fastener, S. W. Alexander	419,097
Basin, waste, overflow, and trap fitting, J. J. Wade	418,831
Basket, fruit, W. A. Clark	418,684
Basket stand, reversible, E. J. Herrick et al.	419,169
Bath tubs, combined supply, overflow, etc., for, F. A. Wells	418,776
Battery. See Secondary battery.	
Battery carbon, C. G. Armstrong	418,837
Battery cut-out, secondary, H. E. Dey	418,701, 418,702
Battery plates, forming secondary, H. E. Dey	418,703
Bed lounge, W. E. Buser	418,971
Bed screen, folding, J. J. Griffith	418,946
Bedstead, A. J. Goodwin	419,118
Beer, Pasteurization of, W. Kuhn	418,872
Bell, door, C. A. Emme	418,975
Bells, striking mechanism for door, E. E. Herrington	419,150
Belt, electric, C. H. Grimley	419,013
Belt gearing, C. W. Wall	418,775
Bench dog, A. A. Tower	418,771
Bicycle stand, G. C. Towle	418,829
Bicycle support, C. Mortson	418,923
Bird trap, B. Walton	418,965
Biscuit machine apron duster, W. Lawrence	418,728
Block. See Toy building block.	
Boot jack, H. W. Farley	418,976
Boot or shoe, W. B. Arnold	418,779
Boot or shoe, W. B. Minahan	418,922
Boot or shoe ventilator, P. Welander	418,936
Bottle stopper, J. A. Edes	418,706
Box. See Journal box. Mailing box. Shipping box. Telegraph alarm box. Work box.	
Box fastener, G. W. Ranker	418,672
Brace. See Hand brace.	
Brake. See Car brake. Vehicle brake. Wagon brake.	
Brake, S. Harris	419,015
Brick machine, W. L. Gregg	419,042
Bridge, suspension, R. E. Akers	418,777
Broiler, W. P. Randall	419,159
Broom brush bridge, J. B. Butenshon	418,941
Buck, saw, M. Jinks	418,861
Bundle tie, Tucker & Smith	418,934
Burner. See Gas burner. Oil burner.	
Button, A. I. Crowell	418,689
Button case and exhibitor, J. H. Morse	418,808
Camera. See Photographic camera.	
Camera stand, E. C. Fisher	419,006
Candy, manufacturing, I. S. Barnett	419,001
Capstan, H. Fletcher	418,786
Capsule note roll, O. Warmuth	418,998
Car brake, Isenberg & Alloway	418,723
Car brake, A. M. Kendall	418,725
Car coupling, W. S. Bales	418,671
Car coupling, J. Bender	418,676
Car coupling, H. Butt	418,680
Car coupling, F. H. Kaye et al.	418,891
Car coupling, F. P. Lenahan	418,731
Car coupling, A. Lynch	418,732
Car coupling, J. A. Mason	418,734, 418,954
Car door, J. Miller	419,057
Car, dumping, Evans & Wilson	418,785
Car, railway, J. McCloy	418,739
Car step, extension, R. H. Brown	419,107
Car, vestibule, J. Ridge	418,929
Car wheel, W. S. Kisiner	418,727
Cars, system of ventilating and heating, E. F. Roberts (r)	11,054
Carding engine, Richard on & Greaves	418,852
Carpet fastener, stair, W. G. Collins	418,972
Carrier system, I. E. Storey	418,856
Case. See Button case. File case. Medicine case. Organ case.	
Caster, J. Ridge	418,928
Castings, core for, W. N. Reddout	418,750
Chain elevator, endless, C. A. Case	418,839
Chair. See Folding chair. Rail chair. Swinging chair. Tilting chair.	
Chair attachment, rocking, C. Kade	418,724
Chair iron, tilting, D. Jenkins	418,917
Check cutter, Pressley & Lumbard	418,961
Cherry seeder, J. C. Magruder	418,733
Churn, P. Kallen	419,127
Cigars, case for exhibiting packages of, B. Baron	419,028
Clasp. See Corset clasp. Spring clasp.	
Clasp tongues, machine for forming, Hisley & Mundy	418,915
Cleaner. See Flue cleaner. Knife cleaner.	
Cloth pressing machine, G. W. Miller	418,805
Cloth pressing machines, brushing attachment for, G. W. Miller	418,804
Clothes line, C. Barlow	418,937
Clothes pin, L. Liebscher	418,918
Coal dumping apparatus, S. Salmon	419,077
Coal loading mechanism, Ely & Salmon	419,145
Coal screening mechanism, Cox & Salmon	419,113
Coffer dam, G. K. Kirkham	418,726
Collar, cuff, etc., apparel, J. R. France	418,787
Collar pad, horse, D. D. Buckles	419,030
Composing stick, A. M. White	418,858

Copy holder, Williams & Thomson	419,026
Corset, E. L. Smith	418,989
Corset clasp, F. B. Converse	418,688
Cotton gin, roller, F. H. Chase	418,908
Counting machine or register, S. T. Bacon	419,100
Coupling. See Car coupling. Hose coupling. Thill coupling.	
Crayon, A. Hart	418,947
Culinary press and grater, combined, E. Baltzley	419,104
Cultivator, C. R. Davis	418,692
Cultivator, J. Lee	418,729
Cultivator, H. Loewenstein	418,931
Cultivator tooth, E. Cutcliffe	418,694
Cultivators, line holder for walking, J. Glor	419,039
Cuspidors, machine for making, C. C. Chamberlain	418,868
Cutter. See Check cutter.	
Dam, portable, S. P. Williams	419,093
Damper regulator, J. B. West	419,090
Dental engine, E. T. Starr	418,901
Desks, ink well for school, G. H. Pumphrey	418,749
Digesters and retorts, discharge door for steam, P. F. Dundon	418,867
Display stand, J. E. Waugh	418,857
Door opening device, W. H. Means	418,736
Dovetail joint, H. L. Andrews et al.	419,133
Draught, device for creating, C. H. Scharar	418,818
Draughtsman's easel, E. Dummer	418,866
Drier. See Hop drier. Lumber drier.	
Drilling apparatus, I. E. Storey	418,854
Drilling machine, W. H. James	418,950
Drilling machine, F. H. Richards	419,070, 419,071
Dust collector, W. E. Allington	418,835, 418,836
Dust collector, Allington & Curtis	418,834
Dust pan, G. H. Ennis	419,115
Dye, blue, B. Homolka	418,916
Dyeing apparatus, J. H. Lorimer	418,801
Dynamos, brush holder for, Claus & Gengenbach	418,685
Ear phone rest, G. E. Christie	418,682
Ejector, fluid, T. E. Jones	419,126
Elastic roll, J. Brinkerhoff	418,886
Electric conductor support, J. B. Smith	418,766
Electric conductors, bracket for supporting, J. A. Duggan	418,704
Electric motor, H. B. Niles	419,059
Electric motor or generator, I. E. Storey	418,853
Electric switch for motors, H. H. Blades	418,678
Electrical energy, transforming and utilizing, M. W. Dewey	418,912
Electricity by secondary batteries, distribution of, G. B. Prescott, Jr.	418,748
Electro-magnetic transmitter, J. T. Williams	419,166
Elevator. See Chain elevator. Hydropneumatic elevator. Water elevator.	
Elevator, Z. Goodell	419,041
Elevator, Hale & Bassett	419,148
Elevator, R. C. Smith	418,878
Elevator or fire escape, H. A. St. Marie	418,827
Engine. See Carding engine. Dental engine. Gas engine. Rotary engine. Steam engine.	
Engine reversing lever, steam, Shearer & McKee	418,760
Fan attachment for velocipedes or other vehicles, C. W. Sommerville	418,933
Farm gate, L. R. Bender	419,002
Faucet, G. W. Miller	419,153
Faucet, whet, E. Wagner, Jr.	418,774
Fence machine, R. J. Aultman	418,667
Fence machine, automatic, W. P. Shattuck	418,759
Fence machine, picket, T. J. Smith	418,990
Fence machine, wire and picket, J. M. Belote	419,136
Fence post, King & Chapman	419,018
Fence post, E. Sims	419,080
Fiber, machine for working vegetable, A. L. Washburn	418,832
Fibrating machine, R. R. Roberts	418,899
File and perforator, letter, E. S. Smith	419,160
File, cabinet, J. Muhlihauser	418,957
File case, rotary letter and paper, E. B. Munday	418,809
Filing papers, safety hook for, L. M. Devore	418,973
Filler, collar, G. B. N. Dow	419,142
Filter, C. V. Roberts	419,023
Filter or strainer, W. A. Hepburn	418,719
Fire escape, L. Anidjah	418,879
Fire escape, W. A. Buckley	419,108
Fire screen, J. W. Griswold	418,713, 418,714
Fish and meat, apparatus for smoking, M. Ams	418,666
Fish line sinker, W. H. Tufts	418,945
Fishing tackle, C. Mayer	419,054
Flanging machine, Munroe & Hamilton	418,983
Flue cleaner, J. A. Hurley	418,722
Flypaper holder for windows, T. Medford	418,803
Fly trap, J. & F. Brunwasser	419,003
Folding chair, C. M. Fetty	419,116
Foot warmer, P. E. McKee	418,743
Frame. See Sign frame.	
Frame house, G. H. Mercer	419,056
Fur robe cleaning machine, F. Hosch	418,842
Furnace. See Heating furnace.	
Furnace, Francis & Manbre	419,007
Furnace, C. F. Miller	418,955
Furnaces, automatic feed for blast, J. Richter	418,927
Furnaces, feed device for ore roasting, A. C. Johnson	418,952
Fuse for projectiles, percussion, W. H. Driggs	419,143
Gauge. See Tack gauge.	
Game apparatus, E. D. Albertson	419,096
Gas, apparatus for making oil, T. Alexander et al.	419,098
Gas blowpipe, D. M. Monroe	418,807
Gas burner for stoves, etc., J. H. Keyser	418,846
Gas engine, J. D. Smith	418,821
Gas, manufacturing, A. O. Granger	418,711
Gas pipes, device for sealing the joints of, W. Rogers	418,752
Gate. See Farm gate. Railway gate.	
Generator. See Steam generator.	
Glass polisher, W. H. Fly	418,707
Glassware, press for forming lenses on articles of, G. B. Barnes	418,881
Grain binder, J. Miller	419,128
Grain binder, L. Miller	419,154
Grain loader and weigher, H. Roberts, Jr.	418,751
Grain meter, P. Barker	418,784
Grain meter, J. Henry	418,735
Grain mills, safety device for, L. Wagner	419,162
Grate, fire, W. Musik	418,810
Grate front, H. D. Pursell	419,064
Grater and chopper, culinary, E. Baltzley	419,101
Grinding, device for holding tools for, J. Blakeslee	418,781
Grinding lawn mower knives, machine for, C. E. Forry	418,977
Gun, breech-loading, J. Jensen	418,951
Gun mounting for field artillery, T. Nordenfelt	418,925
Hame fastening, D. B. Baker	418,689
Hand brace, J. M. Baldwin	419,102
Handle. See Jug handle.	
Harness attachment, F. M. Hall	419,044
Harness attachment, C. J. Ries	419,075
Harrow, O. K. Oppen	419,158
Harvesting and binding machine, J. Miller	418,896
Hay press, T. T. Mayes	418,735
Hay stacking machine, D. H. Talbot	419,025
Head rest, Anderson & Hope	418,935

Head rest and cane, combined, T. S. Minnis..... 418,806  
 Heater. See Sad iron heater. Soldering iron heater. Tank heater.  
 Heating furnace, J. Lawyer..... 419,049  
 Hoisting and conveying apparatus, E. Day..... 419,004  
 Holdback, vehicle, C. W. Colony..... 419,140  
 Holder. See Copy holder. Fly paper holder. Lamp holder. Pen holder. Photo-plate holder. Sash holder. Work holder.  
 Hollow mill, M. Weiss..... 418,903  
 Hook. See Snap hook.  
 Hook, L. M. Devore..... 419,141  
 Hoop. See Toy hoop.  
 Hop drier, W. L. Leechman..... 418,730  
 Horse checking device, W. P. Smith..... 419,082  
 Hose coupling, C. B. Bosworth..... 418,906  
 House. See Frame house.  
 Huller. See Oat huller.  
 Hydropneumatic elevator, C. R. Otis..... 418,875  
 Ice creeper, Voorhis & Starr..... 418,830  
 Ice house, refrigerating, F. Sommers..... 419,131  
 Indicating apparatus electrical, G. A. Holt..... 418,871  
 Ingot pusher, S. T. Wellman..... 418,999  
 Ingot, seamless plated, J. L. P. Spooner..... 419,055  
 Ingots for plated wire, making, J. L. P. Spooner..... 419,084  
 Ingots, mould for making compound metal, J. L. P. Spooner..... 418,767  
 Inhaler, G. L. McQuigg..... 418,813  
 Injector, Holden & Brooke..... 419,047  
 Inkstand, M. Schreiber..... 418,988  
 Insulated nippers, F. M. Casey..... 419,111  
 Iron. See Chair iron.  
 Ironing and polishing machine, C. O. White..... 419,164  
 Ironing machine, C. L. Smith..... 418,765  
 Jack. See Boot jack. Wagon jack.  
 Jaw trap, C. B. Trumble..... 418,772  
 Joint. See Dovetail joint.  
 Journal box, E. L. Post..... 418,990  
 Jug handle and stopper, combined, S. L. Bray..... 418,940  
 Knife cleaner, J. Thompson..... 418,964  
 Knitting machine, circular, Huse & Carr..... 419,151  
 Knives, forming table, E. Grah..... 418,710  
 Lambrequin pin, J. Day..... 418,698  
 Lamp, J. E. Bohner..... 418,782  
 Lamp, electric arc, E. C. Russell..... 418,987  
 Lamp, electric arc, C. E. Scribner..... 418,757  
 Lamp holder, incandescent, I. E. Storey..... 418,855  
 Lasting and tacking machine, Dean & Mundell..... 418,698  
 Lasting machine, H. W. Dean..... 418,694  
 Lathe for turning spirals, M. Brochu..... 419,167  
 Lathe, turning, C. W. McDaniel..... 419,155  
 Lever, J. Buckley..... 418,907  
 Life buoy, G. H. Lidbeck..... 418,897  
 Life preserver, O. Quist..... 419,066  
 Life saving belt, J. C. Wilcox..... 419,182  
 Lightning arrester, E. A. Sperry..... 418,824  
 Limb, artificial, H. M. Kolbe..... 419,019  
 Liquid heater, steam, J. F. Bradford..... 418,989  
 Liquid separator, D. Parks, Jr..... 418,984  
 Lock. See Nut lock.  
 Lock, C. D. Williams..... 419,091  
 Lock and key, R. Tancos..... 418,902  
 Loom positive shuttle motion, S. C. & F. L. Burnham..... 418,863  
 Loom shuttle, A. Baldwin..... 418,670  
 Low water alarm for boilers, Funk & Zeller..... 419,038  
 Lumber drier, C. R. Van Osdel..... 418,773  
 Mailing box, C. Folsom..... 419,117  
 Mantel, sheet metal, J. Graves..... 418,788  
 Match boxing machine, D. Casey & Co..... 418,887  
 Measures, drain cabinet for liquid, C. F. Mowll..... 418,738  
 Mechanical movement, E. B. Cox..... 419,037  
 Mechanical movement, Cox & Salmon..... 419,035  
 Mechanical movement, J. R. Wagner..... 419,069  
 Medicine case, alternating, W. Hawn..... 418,793  
 Merry-go-round, etc., F. W. Aliehin..... 418,833  
 Metal, machine for forming and bending, I. S. McGlehan..... 419,156  
 Metallic plates, apparatus for the manufacture of articles from, S. Fox..... 418,969  
 Meter. See Grain meter.  
 Milk, device for aerating, Morgan & Gates..... 418,695  
 Mill. See Hollow mill.  
 Mould. See Anvil mould.  
 Mortising machine, R. S. & R. L. Greenlee..... 418,978  
 Mosaic work, producing, A. H. Hettich..... 418,840  
 Motion, device for transmitting, J. M. Williams..... 419,092  
 Motor. See Electric motor. Vehicle motor. Wave motor.  
 Motor, J. S. Lester..... 419,051  
 Musical instrument, L. Campiche..... 418,681  
 Nail, W. V. Kay..... 418,844  
 Negative, direct printed adhesive, J. Baynes..... 418,875  
 Nut lock, I. S. Humbert..... 418,949  
 Oat huller, L. C. Dibert..... 418,865  
 Oil burner, injector, H. L. Marbach..... 419,020  
 Ointment for goller, H. H. Hayssen..... 418,717  
 Ordnance sight, H. H. Grenfell..... 418,789  
 Organ case, O. C. Whitney..... 419,000  
 Oven for stoves or ranges, W. L. McDowell..... 419,021  
 Oxygen, apparatus for the production of, L. Chapman..... 418,864  
 Packing for pistons, piston rods, etc., E. B. Cox..... 419,034  
 Packing, piston rod, W. S. Rhodes..... 419,069  
 Packing, rod, F. P. Martin..... 418,802  
 Pad. See Collar pad. Wax pad.  
 Padlock, W. H. Bramble..... 418,894  
 Paint composition, J. Ballinger..... 419,106  
 Pan. See Dust pan.  
 Paper box making machine, Cushman & Taylor..... 418,690  
 Paper feeding device, Crane & Bradshaw..... 418,942  
 Paper flour sack, W. A. Lorenz..... 418,919  
 Patterns, manufacturing transparent, J. Baynes..... 418,674  
 Pen, fountain, W. B. Purvis..... 419,065  
 Pen holder, J. H. Spingener..... 419,063  
 Pen holder, electric, C. W. Reitler (r)..... 11,053  
 Pencil sharpener, E. Bernhardt..... 418,888  
 Pencil sharpener, C. B. Wamaker..... 418,997  
 Pharaoh's serpent, C. Nelson..... 418,814  
 Photo-plate holder, J. Barnett..... 419,105  
 Photographic camera, C. R. Smith..... 418,764  
 Piano action, P. D. Strauch..... 418,769  
 Pierment, black, A. G. Wass..... 419,163  
 Pin. See Clothes pin. Lambrequin pin.  
 Pinchers, lasting, A. Siegel..... 418,762  
 Pipe. See Gas blowpipe. Tobacco pipe.  
 Pipe rack, C. H. Colt..... 419,112  
 Pipes, automatic shut-off for water, H. A. Skinner..... 418,900  
 Planing machine beading attachment, E. C. Mershon..... 418,920  
 Planter, corn, H. Prather..... 418,747  
 Planter, corn, J. W. Spangler..... 418,823  
 Planter, corn, J. M. Young..... 419,095  
 Plow, L. B. White..... 419,165  
 Plow attachment, cotton, J. T. Collier..... 418,696  
 Pole or curtain ring, H. E. Swift..... 418,992  
 Post. See Fence post.  
 Postmarking and stamp canceling machine, W. Groth..... 419,014  
 Power. See Tide power.  
 Press. See Culinary press. Hay press.  
 Printing fabrics with sock, W. H. Locke, Jr..... 418,800

Printing machine and means for preventing offset in the same, perfecting, J. T. Hawkins..... 418,979  
 Printing machines, means for preventing offset in perfecting, J. T. Hawkins..... 419,017  
 Printing machines, offset roller for perfecting, J. T. Hawkins..... 418,980  
 Printing press attachment, A. Ditson..... 418,944  
 Pruning implement, P. Hess..... 418,720  
 Pug mills, elevator for, J. H. Steele..... 418,962  
 Puller. See Thistle puller.  
 Pump, Furber & Ayer..... 418,709  
 Pump, G. G. & T. T. Patchel..... 418,745  
 Pump, duplex, A. Falkenau..... 419,147  
 Punch, bank check, Smith, Jr., & Williamson..... 419,161  
 Punch, check, S. S. Williamson..... 418,905  
 Rack. See Pipe rack.  
 Rail chair, girder, F. P. Reilly..... 418,986  
 Rail, guard, F. M. Parmelee..... 419,022  
 Railway chairs, securing rails in, J. Harrison..... 418,891  
 Railway curved track, H. M. Lane..... 418,798  
 Railway gate, E. L. Edmondson..... 419,144  
 Railway point and signal levers, interlocking, J. P. O'Donnell..... 419,157  
 Railway rail, Stewart & Faw..... 419,086  
 Railway signal, cable, J. H. Pendleton & Co..... 418,850  
 Railway switch, Parlow & Tobey..... 419,061  
 Railway systems, electric heating apparatus for electric, M. W. Dewey..... 418,911  
 Railway tie, W. H. Bagby..... 419,101  
 Railway track fastening, C. A. Harvey..... 418,892  
 Railways, automatic switch for street, H. W. Libbey..... 419,052  
 Range, heating and ventilating, H. Howe..... 419,125  
 Repeating and moulding machine, W. L. Gregg..... 419,043  
 Refrigerator, L. Scofield..... 418,819  
 Regulator. See Damper regulator.  
 Ring. See Pole or curtain ring.  
 Ring, J. H. McIntire..... 418,812  
 Roller, harrow, and marker, combined, J. W. Titus..... 418,828  
 Rolling mill plant, W. Garrett..... 419,008  
 Roofing, composite, D. Harger..... 419,120  
 Roofing, metallic, H. Anderson..... 418,860  
 Rotary engine, T. R. Almond..... 418,665  
 Rotary engine, A. N. Parnall..... 419,062  
 Rule, triangular, Benzinger & Grabau..... 418,967  
 Ruler and pencil sharpener, combined, J. T. Hazlett..... 418,870  
 Sad iron heater, J. A. Bourry..... 418,970  
 Salt making apparatus, F. Siedentopf..... 418,761  
 Sash balance, Headen & Farmer..... 418,948  
 Sash balance, J. McArthur..... 418,811  
 Sash fastener, J. D. Ferree..... 418,914  
 Sash holder, J. A. Baldwin..... 419,134  
 Sawmill dog, G. M. Hinkley..... 419,046  
 Saw setting machine, B. McIntire..... 418,874  
 Saw sharpening machine, L. P. Halladay..... 418,790  
 Saw swage, L. P. Halladay..... 418,715  
 Saw swaging machine, O'Connor & Leduc..... 418,958  
 Saw table clamping device, J. Balsley..... 418,936  
 Scales, automatic weighing, M. B. Bartlett..... 418,882  
 Scales, coin controlled weighing, Smith & Washburn..... 418,822  
 Scales, prescription, C. H. Fitch..... 418,708  
 Screen. See Bed screen. Fire screen.  
 Seaming machine, can, F. M. Leavitt..... 419,050  
 Secondary battery, H. E. Dey..... 418,700  
 Securing or fastening device, T. A. Bristow..... 419,029  
 Separating apparatus, W. Rader..... 419,067  
 Separator. See Liquid separator.  
 Sewer trap, H. A. Palmer..... 418,816  
 Sewing machine, Dimond & Steward..... 418,800  
 Sewing machine, C. F. Harlow..... 418,716  
 Sewing machine, E. H. Smith..... 418,890  
 Sewing machine loop taker cast-off, F. T. Lellich..... 418,836  
 Sewing machine, rotary shuttle, F. T. Lellich..... 418,836  
 Sewing or embroidering machines, cutting and grinding device for, E. Cornely..... 418,909  
 Shipping box, knockdown, M. E. Campany..... 419,109  
 Sifter and safe, ash, I. D. Crispell..... 419,114  
 Sign, C. Schwartz..... 418,755  
 Sign frame, C. Schwartz..... 418,756  
 Signal. See Railway signal.  
 Signal apparatus, interlocking, J. Hill & Co..... 419,170  
 Signaling apparatus, switch, A. Barnes..... 419,135  
 Signal operating device, electrical, C. A. & J. F. Cox..... 418,910  
 Sluiceway and flood gate, T. Parker..... 418,876  
 Snap hook, O. C. Gilmore..... 419,011  
 Snow plow, rotary, J. W. Houghawout..... 419,149  
 Soldering iron heater, W. Nehring..... 419,058  
 Soldering tool, C. L. Wagandt..... 418,934  
 Sounder, electric deep sea, Cooper & Wigzell..... 418,889  
 Spiles, apparatus for cutting and trimming, P. Trost..... 418,993  
 Spinning machine spindle driving mechanism, C. W. Jones..... 418,707  
 Spinning spindle support, C. D. McDuffin..... 418,740  
 Spring. See Vehicle spring.  
 Spring clasp, J. Nasse..... 418,924  
 Spring motor for vehicles, F. J. Niswonger..... 419,000  
 Square, T. Benzinger & Grabau..... 418,969  
 Stair rod securer, Walker & Collins..... 418,996  
 Stamp, electro-mechanical time, C. A. Randall..... 419,068  
 Stand. See Basket stand. Bicycle stand. Camera stand. Display stand.  
 Steam engine, J. A. Lidback..... 419,053  
 Steam generator, L. & C. Steinmuller..... 418,825  
 Steering apparatus, steam and hand, W. Miller..... 418,921  
 Stereotype plates, key for securing, D. Reid..... 418,985  
 Stereotype shaving machine, G. E. Lloyd..... 418,799  
 Stopper. See Bottle stopper.  
 Store service apparatus, A. B. Park..... 418,927  
 Stove, G. F. Higgins..... 419,122  
 Stove, cooking, J. A. Price..... 418,851  
 Stove grate, J. J. Graves..... 419,012  
 Stove grate, W. C. Metzner..... 418,848  
 Stove, oil, Goldstein & Block..... 419,040  
 Stove oven, Hoogerzell, Jr., & Hinkley..... 418,721  
 Stove oven, cooking, J. A. Price..... 418,817  
 Stovepipe thimble and ventilator, combined, E. J. Colby..... 418,788  
 Swinging chair, Jones & Bothwell..... 419,152  
 Switch. See Electric switch. Railway switch.  
 Tablet for rapid writing, U. Smith..... 418,991  
 Tack feeding tube, H. W. Dean..... 418,895  
 Tacking machine, H. W. Dean..... 418,697  
 Tank. See Vinegar tank.  
 Tank heater, K. McLennan..... 418,744  
 Telegraph alarm box, district, C. G. Armstrong..... 418,778  
 Thistle puller, M. Drexler..... 418,913  
 Thill coupling, M. G. Hawke..... 419,016  
 Thrashing machine, Starkey & Vernier..... 418,788  
 Thrashing machine shoe, H. Bryan..... 418,852  
 Thrashing machines, fan and canopy attachment for, Parker & McCay..... 419,123  
 Tide power, D. S. Early..... 418,705  
 Tie. See Bundle tie. Railway tie.  
 Tilting chair, T. J. Collins..... 418,687  
 Tire for vehicle wheels, H. M. Du Bois..... 419,005  
 Tire for vehicles, rubber, F. E. Lyon..... 418,982  
 Tobacco pipe, G. C. Eastman..... 418,974  
 Toe weight, E. L. Gregg..... 418,945

Tool, combination, W. J. McFeely..... 418,742  
 Toy bowling alley, J. Meindl..... 418,737  
 Toy building block, J. W. Arold..... 419,099  
 Toy hoop, Branagan & Martineau..... 418,885  
 Track gauge, J. J. Griffith..... 418,712  
 Transportation, system of, B. S. Henning..... 418,718  
 Trap. See Bird trap. Fly trap. Jaw trap. Sewer trap.  
 Trestle, extensible, G. & R. J. Bogusch..... 418,938  
 Truck, Bakenhus & Mueseler..... 418,838  
 Truck, car, P. J. Boris..... 419,139  
 Tube. See Tack feeding tube.  
 Tubular and other bodies, securing trimmings upon, P. Gendron..... 419,009  
 Tug, shaft, H. F. Bock..... 418,679  
 Type setting machine, J. Gustafson..... 419,119  
 Typewriting machines, type aligner for, A. W. Hallenborg..... 418,791  
 Umbrella, C. H. Knubel..... 418,845  
 Umbrella support, L. E. Bobemerith..... 419,137  
 Valve, L. Roovers..... 419,076  
 Valve gear, engine, R. F. McFeely..... 418,741  
 Vehicle brake, L. M. Carpenter..... 419,110  
 Vehicle, electrically propelled, R. M. Hunter..... 418,893  
 Vehicle running gear, C. W. Saladee..... 418,753  
 Vehicle, spring, A. Schubert..... 418,931  
 Vehicle spring, H. C. Swan..... 419,170  
 Vehicle wheel, H. E. West..... 418,904  
 Vehicles by electricity, apparatus for propelling, F. Wynne..... 419,094  
 Vehicles, means for the electrical propulsion of, D. E. Johnson..... 418,843  
 Velocipede, A. M. Stoner..... 418,963  
 Ventilator. See Boot or shoe ventilator.  
 Vinegar tank, J. Doran..... 418,784  
 Vise, bench, H. Liefer..... 418,847  
 Vise, milling machine, F. H. Richards..... 419,072  
 Wagon, J. C. Huhn & Co..... 418,796  
 Wagon body, C. T. Evans..... 419,146  
 Wagon brake, M. L. Haskins..... 419,045  
 Wagon brage, W. S. Smith..... 419,081  
 Wagon dump, J. Simpson..... 418,763  
 Wagon jack, J. Burne..... 419,031  
 Wagon running gear, P. Gendron..... 419,010  
 Washing machine, J. W. Bader..... 418,668  
 Washing machine, B. C. Phillips..... 419,063  
 Water elevator, G. M. Atherton..... 418,861  
 Water on land, means for controlling the shifting action of moving, G. H. Henshaw..... 419,121  
 Wave motor, R. B. Davy..... 418,943  
 Wax pad, A. R. Sherwood..... 419,079  
 Way bills, etc., cover for, G. H. Ogden..... 418,815  
 Weaver, calf, S. E. Shaw..... 419,078  
 Weatherboards, adjustable gauge for supporting, H. Schill..... 418,754  
 Welding by electricity, C. L. Coffin..... 419,032  
 Well boring apparatus, E. F. Littlepage..... 418,873  
 Wheel. See Car wheel. Vehicle wheel.  
 Wheel, G. H. Bartlett..... 418,673  
 Whip, G. Pirnie..... 419,190  
 Whip socket and rein holder, combined, F. Tompkins..... 419,087  
 Windmill, W. J. Hogue..... 419,123  
 Windmill, F. T. Zimmerman..... 418,859  
 Windmill, S. D. Straw..... 419,024  
 Windmill governor, A. J. Salisbury..... 418,877  
 Window cleaning implement, G. Pilon..... 418,959  
 Window grate, A. S. Jordan..... 419,048  
 Wire stretcher, O. D. Hearn..... 418,794  
 Woodworking machines, clamping mechanism for, J. Balsley..... 418,890  
 Work box, H. W. Clapp..... 418,683  
 Work holder, F. H. Richards..... 419,073  
 Yeast cakes, machine for making, O. S. Hoffman..... 418,841  
 Yoke, poke, A. Holding..... 419,188

**DESIGNS.**  
 Billiard table, H. Bonninghausen..... 19,560  
 Burial casket, W. J. Noble..... 19,567  
 Carriages, fabric for children's, J. R. Martineau..... 19,566  
 Check rein hook, P. Gschwend..... 19,568  
 Handle for sleighs, doors, etc., G. S. Caldwell..... 19,561  
 Hoe, weeding, J. W. Douglas..... 19,562  
 Latch case, G. S. Barkentin..... 19,563  
 Match box, H. P. Fairchild..... 19,568  
 Money box, Newman & Bennett..... 19,569  
 Printed fabric, S. W. Johnson..... 19,564  
 Residence, exterior of a, W. K. Benedict..... 19,554  
 Residence, exterior of a, A. Lacroix, Jr..... 19,566  
 Sash cord guide face plate, S. Palmer..... 19,570  
 Show case, F. H. Starling..... 19,571

**TRADE MARKS.**  
 Baking powder, J. H. Brookmire & Co..... 17,862  
 Baking powder, T. H. Bros..... 17,887  
 Brushes, tooth, Newman & Kinkle..... 17,381  
 Buttons of jet and metal, L. Prange..... 17,383  
 Chocolates, desiccated coconut, jellies, and candies, C. B. Miller..... 17,379  
 Coffee and tea of all kinds, J. H. Brookmire & Co..... 17,363  
 Crackers and biscuits, Lone Star Cracker and Manufacturing Company..... 17,377  
 Face powder, A. L. V. Wood..... 17,389  
 Fumigating compound or pastilles, A. J. Ostheimer..... 17,382  
 Gum, chewing, Malena Co..... 17,378  
 Gum, chewing, W. W. Morris..... 17,380  
 Hostery, H. B. Claflin & Co..... 17,364  
 Lard, C. F. Ferrer..... 17,368  
 Locks, Beasley Supply Company..... 17,360  
 Medical compound for the cure of cholera, asthma, bronchitis, consumption, dyspepsia, rheumatism, paralysis, diarrhea, and diseases of the blood, C. R. King..... 17,374  
 Medical preparations for veterinary purposes, E. H. Kohne..... 17,375  
 Ointment, pils, Gassner & Gust..... 17,371  
 Paints, prepared, Western Paint Co..... 17,388  
 Perfumery, J. J. Healy..... 17,372  
 Preserved foods, including desserts, fruits, and jellies for soups, R. F. S. Heath..... 17,373  
 Salve, N. O. Lawson..... 17,376  
 Seeds, timothy, Conklin & Mesereau..... 17,367  
 Silk plushes and silk seals, Brigg, Neumann & Co..... 17,361  
 Tea, Sherman Bros. & Co..... 17,384  
 Tobacco pipes and cigars and cigarette tubes and holders, A. Frankan & Co..... 17,369  
 Whisky, J. Tharp..... 17,386  
 Wire, barbed, Freeman Wire and Iron Company..... 17,370  
 Wire picture and sash cord and bonnet and flower wire, Tate & Co..... 17,385

A Printed copy of the specification and drawing of any patent in the foregoing list will be furnished from this office for 25 cents. In ordering please state the name and number of the patent desired, and remit to Munn & Co., 361 Broadway, New York.

Canadian Patents may now be obtained by the inventors for any of the inventions named in the foregoing list, provided they are simple, at a cost of \$40 each. If complicated, the cost will be a little more. For full instructions address Munn & Co., 361 Broadway, New York. Other foreign patents may also be obtained.

## Advertisements.

Inside Page, each insertion - - - 75 cents a line.  
 Back Page, each insertion - - - \$1.00 a line.  
 The above are charges per agate line—about eight words per line. This notice shows the width of the line, and is set in agate type. Engravings may head advertisements at the same rate per agate line, by measurement, as the letter press. Advertisements must be received at publication office as early as Thursday morning to appear in next issue.

## USE ADAMANT WALL PLASTER

It is Hard, Dense, and Adhesive. Does not crack or peel. It is impervious to wind, water, and disease germs. It dries in a few hours. It can be applied in any kind of weather. It is in general use. Licenses granted for the mixing, using, and selling.  
 Address ADAMANT MFG. CO.  
 309 E. Genesee St.,  
 Syracuse, N. Y.

Seneca Falls Mfg. Co., 695 Water St., Seneca Falls, N. Y.

**LATHE**  
 Foot Lathe Swings 9x25 in.  
 \$75  
 Catalogue Free of all our Machinery.

**SEBASTIAN, MAY & CO'S**  
 Improved Screw Cutting  
**Foot & Power LATHES**  
 \$60  
 Drill Presses, Chucks, Drills, Dogs, and machinists' and amateurs' outfits. Lathes on trial. Catalogues mailed on application.  
 165 W. 2d St., Cincinnati, O.

**ENTERTAIN**  
 TEACH YOURSELF  
 IMPROVED LIME LIGHT SETS OF OIL & MAGIC LANTERNS  
 VIEWS WITH PRINTED LECTURES  
 J. B. COLT & CO.  
 16 BECKMAN ST. NEW YORK

**SPECIAL NOTICE!**  
 We have just issued a Catalogue and Price List of Mining, Tunneling, and Quarrying Machinery. This catalogue will be mailed free to contractors, engineers, and to any one engaged or interested in rock excavation or compressed air. To all other persons it will be sent on receipt of 50 cents in postage stamps.  
 INGERSOLL-SERGEANT ROCK DRILL CO.,  
 10 Park Place, New York.

**ROCK DRILLS**  
**AIR COMPRESSORS & GENERAL MACHINERY**  
**MINING, TUNNELING, QUARRY & RAILROAD WORK**  
**RAND DRILL CO. 23 PARK PLACE NEW YORK**

**CABINET WOODS and VENEERS,**  
**FRET SAW or BRACKET WOODS**  
**PLANNED READY FOR USE**  
 Send stamp for catalogue.  
**HENRY T. BARTLETT, 200 LEWIS STREET, NEW YORK.**

**CATALOGUES FREE TO ANY ADDRESS**  
**TOOLS OF ALL KINDS**  
 GOODNOW & NIGHTMAN BOSTON

**\$3 PRINTING PRESS**  
 For cards, labels, etc. Circular press, \$3. Size for small newspapers, \$4. Rotary jobber, \$13, \$100. Do all your own printing and advertising. Full printed rules for type-setting, etc. Send 2 stamps for catalogue of presses, type, cards, etc. to factory. **KELSEY & CO., Meriden, Conn.**

**STEEL TYPE for TYPEWRITERS,**  
 Stencils, Steel Stamps, Rubber and Metal Type Wheels.  
**New York Stencil Works, Mfrs.**  
 100 Nassau Street, New York.

**CANALIZATION OF RIVERS. —** Description of the methods employed in canalizing the river Seine. With 5 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 689. Price 10 cents. To be had at this office and from all newsdealers.

**ASBESTOS**  
 MINERS & MANUFACTURERS.  
 The ASBESTOS PACKING CO.  
 169 CONGRESS ST. BOSTON

**ICE-HOUSE AND COLD ROOM. —** BY R. G. Hatfield. With directions for construction. Four engravings. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 689. Price 10 cents. To be had at this office and from all newsdealers.

**TOOL AGENTS WANTED**  
 in every SHOP in the United States.  
 Send 10c for catalogue. Stationery &c.  
**THE FINEST OF MECHANICAL TOOLS A SPECIALTY.**  
**C. E. JAMES, 98 LAKE ST. CHICAGO.**

**PRESSES. 50 to 500 TONS,**  
 by Hand or Power.  
 For almost every purpose requiring pressure.  
**BOOMER & BOSCHERT PRESS CO.**  
 Send for Catalogue.  
 155 West Water Street,  
 Syracuse, N. Y., U. S. A.



## A Great Repository of Practical and Scientific Information.

One of the Fullest, Freshest, and Most Valuable Handbooks of the Age. Indispensable to Every Practical Man.

**NOW READY.**

Price \$2.00.

Free of Postage to any Address in the World.

## The Techno-Chemical Receipt Book:

Containing Several Thousand Receipts, covering the Latest, most Important, and most Useful Discoveries in Chemical Technology, and their Practical Application in the Arts and the Industries. Edited chiefly from the German of Drs. Winckler, Eisner, Heintze, Mierzinski, Jacobsen, Koller, and Heintze, with additions by William T. Brant, Graduate of the Royal Agricultural College of Edinburg, Prussia, and William H. Wahl, Ph.D. (Heid.), Secretary of the Franklin Institute, Philadelphia, author of "Galvanoplastic Manipulations." Illustrated by 78 engravings, one volume, over 500 pages, 12mo, elegantly bound in scarlet cloth, gilt, closely printed, containing an immense amount and a great variety of matter.

Price \$2.00, free of postage to any address in the world. A circular of 32 pages, showing the full Table of Contents of this important book, sent by mail free of postage to any one in any part of the World who will furnish his address.

**HENRY CAREY BAIRD & CO.**  
INDUSTRIAL PUBLISHERS, BOOKSELLERS & IMPORTERS  
810 Walnut St., Philadelphia, Pa., U.S.A.

## ARCHITECTURAL BOOKS.

Useful, Beautiful, and Cheap.

To any person about to erect a dwelling house or stable, either in the country or city, or any builder wishing to examine the latest and best plans for a church, school house, club house, or any other public building of high or low cost, should procure a complete set of the ARCHITECTS' AND BUILDERS' EDITION of the SCIENTIFIC AMERICAN.

The information these volumes contain renders the work almost indispensable to the architect and builder, and to persons about to build for themselves they will find the work suggestive and most useful. They contain colored plates of the elevation, plan, and detail drawings of almost every class of building, with specification and approximate cost.

Eight bound volumes are now ready and may be obtained, by mail, direct from the publishers or from any newsdealer. Price, \$2.00 a volume. Stitched in paper covers. Subscription price, per annum, \$2.50. Address and remit to

**MUNN & CO., Publishers,**  
361 Broadway, New York.

**HOME-MADE INCUBATOR.**—PRACTICAL directions for the manufacture of an effective incubator that has been carefully tested and found to perform all that may be reasonably expected; with directions for operating. With 4 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 634. Price 10 cents. To be had at this office and from all newsdealers.

**WEITMYER PATENT FURNACE. BOILERS OF EVERY DESCRIPTION. IDE AUTOMATIC ENGINES. Traction and Portable Engines. STEAM ROAD ROLLERS.**  
Manufactured by FOUNDRY & MACHINE DEPT., Harrisburg, Pa., U. S. A.

**CUTLER DESK. BEST IN THE WORLD.**  
A. CUTLER & SON, BUFFALO, N. Y., U. S. A.

## IS YOUR LIFE SAFE AT HOME?



Now is the season of the year when your house is shut up and you are liable to breathe impure air from a lack of sufficient ventilation. This breeds disease, and is absolutely dangerous to those who do not get plenty of out-door air.

Every Family should have the Sherman 'King' Vaporizer. This simple and inexpensive device purifies the air in every place indoors.


It Never Fails. Especially needed in Schools and Churches. Send for particulars.

SHERMAN "KING" VAPORIZER CO., Chicopee Falls, Mass.

## TYPEWRITERS

Send for New Illustrated Catalogue describing all Machines. Largest stock in America. New or Second-hand Typewriters of all makes. Machines Rented in any part of the country. Supplies in abundance. Prices the lowest.

**NATIONAL TYPEWRITER EXCHANGE,**  
161 La Salle Street, Chicago, Ill.



## A PRACTICAL SUCCESS.


VAN DUZEN'S PAT. LOOSE PULLEY OILER.

Thousands in satisfactory everyday use. Entire reliability and constant demonstrated in a two years' test (by would be) Eastern skeptics. Economy shown by reasonable prices and perfect performance. Send for our "Catalogue No. 55."

VAN DUZEN & TIFT, Cincinnati, O.


## 2nd MACHINERY

N. Y. Mach'y Depot, Bridge Store 18, Frankfort St., N. Y.



NOW READY.

## Experimental Science,



BY GEO. M. HOPKINS.

740 Pages. 680 Illustrations.

PRICE, by mail, postpaid, . . . \$4.00


SEND for FREE ILLUSTRATED CIRCULAR and Table of Contents.

MUNN & CO., Publishers,

Office of The Scientific American,

361 Broadway, New York.

## WATCHMAN'S Improved TIME DETECTOR



with Safety Lock Attachment. Patented 1875-6-7-80-81. Beware of imitations. This instrument is supplied with 12 keys for 12 stations. Invaluable for all concerns employing night watchmen. Send for circulars to R. HAUSER, P.O. Box 2875, 206 and 208 Broadway New York.

## PILE DRIVING MACHINERY!

Send for 1890 catalogue. Vulcan Iron Works, 80 N. Clinton St., Chicago.

WORKING MODELS & LIGHT MACHINERY. INVENTIONS DEVELOPED. Send for Model Circular. Jones Bros. E. Co., Cin. O.

## FOREIGN PATENTS

THEIR COST REDUCED.

The expenses attending the procuring of patents in most foreign countries having been considerably reduced the obstacle of cost is no longer in the way of a large proportion of our inventors patenting their inventions abroad.

**CANADA.**—The cost of a patent in Canada is even less than the cost of a United States patent, and the former includes the Provinces of Ontario, Quebec, New Brunswick, Nova Scotia, British Columbia, and Manitoba.

The number of our patentees who avail themselves of the cheap and easy method now offered for obtaining patents in Canada is very large, and is steadily increasing.

**ENGLAND.**—The new English law, which went into force on Jan. 1st, 1885, enables parties to secure patents in Great Britain on very moderate terms. A British patent includes England, Scotland, Wales, Ireland and the Channel Islands. Great Britain is the acknowledged financial and commercial center of the world, and her goods are sent to every quarter of the globe. A good invention is likely to realize as much for the patentee in England as his United States patent produces for him at home, and the small cost now renders it possible for almost every patentee in this country to secure a patent in Great Britain, where his rights are as well protected as in the United States.

**OTHER COUNTRIES.**—Patents are also obtained on very reasonable terms in France, Belgium, Germany, Austria, Russia, Italy, Spain (the latter includes Cuba and all the other Spanish Colonies), Brazil, British India, Australia, and the other British Colonies.

An experience of over FORTY years has enabled the publishers of THE SCIENTIFIC AMERICAN to establish competent and trustworthy agencies in all the principal foreign countries, and it has always been their aim to have the business of the clients promptly and properly done and their interests faithfully guarded.

A pamphlet containing a synopsis of the patent laws of all countries, including the cost for each, and other information useful to persons contemplating the procuring of patents abroad, may be had on application to this office.

MUNN & CO., Editors and Proprietors of THE SCIENTIFIC AMERICAN, cordially invite all persons desiring any information relative to patents, or the registry of trade-marks, in this country or abroad, to call at their offices, 361 Broadway. Examination of inventions, consultation, and advice free. Inquiries by mail promptly answered.

Address, **MUNN & CO.,**  
Publishers and Patent Solicitors,  
361 Broadway, New York.

BRANCH OFFICES: No. 622 and 624 F Street, Pacific Building, near 7th Street, Washington, D. C.

**CLARK'S NOISELESS RUBBER WHEELS.**  
Absolutely prevents splintering and wearing of floors caused by use of iron wheels. Adapted for Trucks, Boxes, Baskets, Tables and work of every kind in Mills, Warehouses, etc. Also furniture casters. Catalogue free. Geo. F. Clark, Box 1, Windsor Locks, Conn.

**Lightning Well-Sinking Machinery.**  
Makers of Hydraulic, Jetting, Revolving, Artesian, Mining, Diamond, Tools, Wells & Prospecting, Engines, Boilers, Wind Mills, Pumps, etc. Sold on Trial. An ENCYCLOPEDIA of 1,000 Engravings, Earth Stratification, Determination of Minerals and Quality of Water. Gives Light, Finds Gold. Gas Book 25 cts. The American Well Works, AURORA, ILL.

## OIL WELL SUPPLY CO. Ltd.

91 & 92 WATER STREET, Pittsburgh, Pa.

Manufacturers of everything needed for ARTESIAN WELLS for either Gas, Oil, Water, or Mineral Tests, Boilers, Engines, Pipe, Cordage, Drilling Tools, etc. Illustrated catalogue, price lists and discount sheets on request.



## ARTESIAN

Wells, Oil and Gas Wells, drilled by contract to any depth, from 60 to 3000 feet. We also manufacture and furnish everything required to drill and complete same. Portable Horse Power and Mounted Steam Drilling Machines for 100 to 600 ft. Send 6 cents for illustrated catalogue. Pierce Artesian and Oil Well Supply Co., 80 Beaver Street, New York.

## MODELS!

Experimental Work, Light and Special Machinery to order. N. ERLANDSEN, 107 Rivington St., New York.

Special Screws, Pipe Cutters, Solid Steel Thumb Tacks, Patented Articles and General Hardware manufactured by Ellis Manufacturing Co., 356 Congress Ave., New Haven, Ct.

## ICE-HOUSE AND REFRIGERATOR.

Directions and Dimensions for construction, with one illustration of cold house for preserving fruit from season to season. The air is kept dry and pure throughout the year at a temperature of from 34° to 36°. Contained in SCIENTIFIC AMERICAN SUPPLEMENT No. 116. Price 10 cents. To be had at this office and of all newsdealers.

## PERFECT NEWSPAPER FILE

The Koch Patent File, for preserving newspapers, Magazines, and pamphlets, has been recently improved and price reduced. Subscribers to the SCIENTIFIC AMERICAN and SCIENTIFIC AMERICAN SUPPLEMENT can be supplied for the low price of \$1.50 by mail, or \$1.25 at the office of this paper. Heavy board sides; inscription "SCIENTIFIC AMERICAN" in gilt. Necessary for every one who wishes to preserve the paper. Address

MUNN & CO., Publishers SCIENTIFIC AMERICAN.

**PULLEYS, HANGERS, PROGRESS MACHINE WORKS, A. & F. BROWN, FRICTION CLUTCHES. 44 Park Place, N. Y.**

**CELEBRATED SUTTON RING PACKING.**  
PIONEER RUBBER PACKING. POSITIVELY ANTI-FRICTION. SPECIALLY ENGINEERED FOR HIGH SPEED ENGINES. SEND FOR CATALOGUE. ADDRESS: ERIE RUBBER CO. ERIE, PA. U. S. A.

## MODELS AND LIGHT METAL WORK.

T. F. WELCH, Circular Free. 8 Medford Street, BOSTON.

**THE PULSOMETER.**—BY PROF. DE Volson Wood. A discussion of the theory of the apparatus and a mathematical analysis of its work. With 1 figure. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 704. Price 10 cents. To be had at this office and from all newsdealers.

## BARNES' PAT. FOOT POWER MACHINERY.

I feel so highly pleased with your Velocipede Foot Power with seat, that I wish to add my testimony to its superiority. I did not expect to like it, but having used the Velocipede Power, I would have nothing else. It so greatly lessens the fatigue of using foot power, in fact, it may be said to be almost without fatigue, and is a steadier motion. I wish I had known of it sooner. Send for catalogue. W. F. & J. BARNES CO., 369 Ruby St., Rockford, Ill.

## Perforated Electric Belting

FOR—**SWIFT RUNNING MACHINERY.**

Write for Descriptive Catalogue to

**CHAS. A. SCHIEREN & CO.**

45-51 FERRY ST., NEW YORK.

## THE PENNA. DIAMOND DRILL & MFG. CO.

BIRDHORO, PA. Builders of High Class Steam Engines, Diamond Drilling and General Machinery. Flour Mill Rolls Ground and Grooved.

## DEAFNESS & HEAD NOISES CURED BY

Peck's INVISIBLE TUBULAR EAR CUSHIONS. Whispers heard, Comfortable. Successful where all Remedies FAIL. Ills. book & proofs free. Address F. HISCOTT, 853 Broadway, New York.



Standard Silverware Co., Boston, Mass.

**Navy Department, Washington, D. C., December 27, 1889.**—Competitive trials of armor plates will be held by the Navy Department at the Naval Ordnance Proving Ground, Annapolis, Md., or at such other place as may be designated. The armor plates submitted must be 6 feet by 8 feet and 10 1/2 inches thick. Those who intend to furnish armor plates for trial can obtain full information concerning the tests by communicating with the Bureau of Ordnance, Navy Department. Notice of intention to compete in this trial must be received by the Bureau of Ordnance on or before February 10, 1890. B. F. TRACY, Secretary of the Navy.

**To Engineers and Contractors.**—OFFICE OF THE LIGHT-HOUSE BOARD, Washington, D. C., January 9, 1890.—Proposals will be received at this office until 12 o'clock noon on Tuesday, the 1st day of July, 1890, for the design, the specifications, the complete construction and equipment and the temporary maintenance of a light-tower on Diamond Shoal, off Cape Hatteras, North Carolina. By an Act of Congress the total cost of the light-station shall not exceed the sum of \$500,000. Specifications embodying the requirements of the structure, forms of proposals, and other information may be obtained on application at this office. The right is reserved to reject any or all bids and to waive any defects. DAVID B. HARMONY, Rear-Admiral U. S. N., Chairman.

## MAGIC LANTERNS

AND STEREOPTICONS SCHOOLS & PUBLIC ENTERTAINMENTS. LANTERN SLIDES COLORED & UNCOLORED. SEND FOR CATALOGUE. **QUEEN & CO.** PHILA. PA.

## ASBESTOS Fire Felt Coverings,

Packings, Sealings, &c. The CHALMERS-SPENCE CO., Mfrs. 419-425 5th Street, East River, N. Y.

## HERTZ'S EXPERIMENTS.—A PAPER

by M. Joubert, discussing the celebrated experiments of Mr. H. Hertz, which have given so much information as to the intervention of the external medium in electrical phenomena. With 2 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 718. Price 10 cents. To be had at this office and from all newsdealers.

## The Scientific American

PUBLICATIONS FOR 1890.


The prices of the different publications in the United States, Canada, and Mexico are as follows:

RATES BY MAIL.	
The Scientific American (weekly), one year	\$3.00
The Scientific American Supplement (weekly), one year	5.00
The Scientific American, Spanish Edition (monthly) one year	3.00
The Scientific American, Architects and Builders Edition (monthly), one year	2.50
COMBINED RATES.	
The Scientific American and Supplement	\$7.00
The Scientific American and Architects and Builders Edition	5.00
The Scientific American, Supplement, and Architects and Builders Edition	9.00
Proportionate Rates for Six Months.	
This includes postage, which we pay. Remit by postal or express money order, or draft to order of	
<b>MUNN &amp; CO., 361 Broadway, New York.</b>	

## Advertisements.

Inside Page, each insertion --- 25 cents a line.  
Back Page, each insertion --- \$1.00 a line.

The above are charges per agate line—about eight words per line. This notice shows the width of the line, and is set in agate type. Engravings may head advertisements at the same rate per agate line, by measurement, as the letter press. Advertisements must be received at publication office as early as Thursday morning to appear in next issue.



Wheeling is Better than Walking.

## Victor Bicycles

Are Better than Any Others.  
Catalogue Free.  
Overman Wheel Co., Makers,  
BOSTON, MASS.

**THE COPYING PAD.—HOW TO MAKE**  
and how to use; with an engraving. Practical directions how to prepare the gelatine pad, and also the aniline ink by which the copies are made; how to apply the written letter to the pad; how to take off copies of the letter. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 438. Price 10 cents. For sale at this office and by all newsdealers in all parts of the country.

## NEW KODAKS



"You press the button,  
we do the rest."

Seven New  
Styles and  
Sizes  
ALL LOADED WITH  
Transparent  
Films.

For sale by all Photo. Stock Dealers.

THE EASTMAN COMPANY,

Sent for Catalogue. ROCHESTER, N. Y.

## THE ONLY PRACTICAL LOW-PRICED TYPEWRITER

Catalogue free. Address Typewriter Department,  
POPE MFG. CO., Makers of Columbia Cycles,  
Boston, New York, Chicago.

**ON GAS ENGINES.—A VALUABLE**  
paper by E. Delamare-Debuterville, touching upon the history of gas engines in general, and describing in detail the "Simplex" engine invented by the author and Mr. Mialandin. With 23 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, Nos. 715 and 716. Price 10 cents each. To be had at this office and from all newsdealers.

## GATES ROCK & ORE BREAKER



Capacity up to 150 yards per hour.

Has produced more ballast, road metal, and broken more ore than all other Breakers combined.

Send for Catalogues.  
**GATES IRON WORKS**  
500 So. Clinton St.,  
CHICAGO.

**THE MODERN ICE YACHT.—BY**  
Geo. W. Polk. A new and valuable paper, containing full practical directions and specifications for the construction of the fastest and best kinds of Ice Yachts of the latest, most approved forms. Illustrated with engravings drawn to scale, showing the form, position, and arrangement of all the parts. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 624. Price 10 cents. To be had at this office and from all newsdealers.

**The CHANDLER**  
**WATER MOTOR**  
as adapted for blowing  
**ORGANS.**  
Automatic, Noiseless.  
Send for Circulars.  
Howard Bros., Buffalo, N. Y.

**SAWS** Wanted 50,000 Sawyers  
**SAWS** send us their full address for a copy of Emerson's Book of SAWS. We are first to introduce NATURAL GAS for heating and tempering SAWS with wonderful effect upon improving their quality and toughness, enabling us to reduce prices. Address  
**EMERSON, SMITH & CO. (Ltd.),**  
Beaver Falls, Pa.

**MAGIC LANTERNS**  
WITH OIL LAMPS HAVE NO EQUAL  
VIEWS OF ALL SUBJECTS  
EASTERN PRICES. JAPANESE  
**L. MANASSE**  
33 MADISON CHICAGO ILL.

## PATENTS!

MESSRS. MUNN & CO., in connection with the publication of the SCIENTIFIC AMERICAN, continue to examine improvements, and to act as Solicitors of Patents for Inventors.

In this line of business they have had *forty-one years' experience*, and now have *unequalled facilities* for the preparation of Patent Drawings, Specifications, and the prosecution of Applications for Patents in the United States, Canada, and Foreign Countries. Messrs. Munn & Co. also attend to the preparation of Caveats, Copyrights for Books, Labels, Reliefs, Assignments, and Reports on Infringements of Patents. All business entrusted to them is done with special care and promptness, on very reasonable terms.

A pamphlet sent free of charge, on application, containing full information about Patents and how to procure them; directions concerning Labels, Copyrights, Designs, Patents, Appeals, Reliefs, Infringements, Assignments, Rejected Cases. Hints on the Sale of Patents, etc.

We also send, free of charge, a Synopsis of Foreign Patent Laws, showing the cost and method of securing patents in all the principal countries of the world.

**MUNN & CO., Solicitors of Patents,**  
361 Broadway, New York.  
BRANCH OFFICES.—No. 62 and 64 F. Street, Patent Building, near 7th Street, Washington, D. C.

## H. W. JOHNS' Asbestos Sectional Pipe Covering



A Non-Conducting Covering for Steam and Hot Water Pipes, etc.  
READILY ATTACHED OR REMOVED BY ANY ONE.

## Asbestos Boiler Coverings.

We are prepared to take contracts for applying Steam Pipe and Boiler Coverings in any part of the United States.

**H. W. Johns Manufacturing Company,**

SOLE MANUFACTURERS OF  
H. W. Johns' Asbestos Millboard, Sheathings, Building Felts, Fire-Proof Paints, Liquid Paints, Asbestos Roofing, etc.

87 Malden Lane, New York. CHICAGO. PHILADELPHIA. LONDON.

**NICKEL AND ELECTRO-PLATING APPARATUS AND MATERIAL**  
HANSON, VAN WINKLE & CO.  
NEWARK, N. J.  
32 LIBERTY ST. N. Y.

## TO BUSINESS MEN

The value of the SCIENTIFIC AMERICAN as an advertising medium cannot be overestimated. Its circulation is many times greater than that of any similar journal now published. It goes into all the States and Territories, and is read in all the principal libraries and reading rooms of the world. A business man wants something more than to see his advertisement in a printed newspaper. He wants circulation. This he has when he advertises in the SCIENTIFIC AMERICAN. And do not let the advertising agent influence you to substitute some other paper for the SCIENTIFIC AMERICAN, when selecting a list of publications in which you decide it is for your interest to advertise. This is frequently done, for the reason that the agent gets a larger commission from the papers having a small circulation than is allowed on the SCIENTIFIC AMERICAN.

For rates see top of first column of this page, or address **MUNN & CO., Publishers,**  
361 Broadway, New York.

**2 to 40 H. P. The MOTOR of 19th CENTURY.**  
Can be used Any Place, to do Any Work, and by Any One. No Boiler! No Fire! No Steam! No Ashes! No Gauges! No Engineer! A perfectly safe Motor for all places and purposes. Cost of operation about one cent an hour to each indicated horse power. For circulars, etc., address  
**Charter Gas Engine Co.,**  
Economy, Reliability, Simplicity, Safety. P. O. Box 148, Sterling, Ill.

**JENKINS STANDARD PACKING**  
TRADE MARK

**HARRISON CONVEYOR!**  
For Handling Grain, Coal, Sand, Clay, Tan Bark, Cinders, Ores, Seeds, &c.  
Send for Circulars. **BORDEN, SELLECK & CO.,** Sole Mfrs., Chicago, Ill.

**VELOCITY OF ICE BOATS.** A COLLECTION of interesting letters to the editor of the SCIENTIFIC AMERICAN on the question of the speed of ice boats, demonstrating how and why it is that these craft sail faster than the wind which propels them. Illustrated with 10 explanatory diagrams. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 214. Price 10 cents. To be had at this office and from all newsdealers.

**THE LUNKENHEIMER BRASS MFG CO.**  
RE-GRINDING GLOBE & CHECK VALVES  
GATE VALVES, POP SAFETY VALVES  
LIGHT FEED, BRICATORS, OIL EXHAUSTERS  
BRASS & PHOSPHOR BRONZE CASTINGS

**THE AMERICAN BELL TELEPHONE CO.**  
95 MILK ST., BOSTON, MASS.

This Company owns the Letters Patent granted to Alexander Graham Bell, March 7th, 1876, No. 174,465, and January 30th, 1877, No. 186,787.

The transmission of Speech by all known forms of Electric Speaking Telephones infringes the right secured to this Company by the above patents, and renders each individual user of telephones not furnished by it or its licensees responsible for such unlawful use, and all the consequences thereof, and liable to suit therefor.


**BARREL, KEG, Hogshead, AND STAVE MACHINERY**  
Over 50 varieties manufactured by  
**E. & B. HOLMES,**  
BUFFALO, N. Y.

**FOR SALE, CHEAP.**—60 Sets of Castings for 4-Horse Power Engines.  
**WINDSOR FOUNDRY,** Windsor, N. Y.

**CRANK AND SCREW SHAFTS OF THE**  
Mercantile Marine.—A paper by G. W. Mansel, discussing some of the causes of the breakage of marine engine shafting, and also some of the remedies that have been tried to reduce the number of such accidents. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 717. Price 10 cents. To be had at this office and from all newsdealers.

**THE FRED'K CRANE CHEMICAL CO.**  
SHORT HILLS, N. J. BOX 91A

## REMINGTON



## STANDARD TYPEWRITER.

Gold Medal—Paris Exposition, 1889.

**Wyckoff, Seamans & Benedict**  
327 BROADWAY, NEW YORK.


**MALLEABLE** AND FINE GRAY IRON ALSO STEEL CASTINGS FROM SPECIAL PATTERNS.  
**THOMAS DEVLIN & CO.**  
LEHIGH AVE. & AMERICAN ST. PHILA.

INVENTORS and others desiring new articles manufactured and introduced, address P. O. Box 86, Cleveland, O.

**POP SAFETY VALVE**  
**WATER RELIEF VALVE**  
**IMPROVED STEAM GAGE**  
**STEAM ENGINE INDICATOR**  
Single Bell Chime Whistle, and all instruments used in connection with Steam, Air and Water.  
Sole Agents for Clark's Laney Fire Hose.  
**CROSBY STEAM GAGE & VALVE CO.** Boston, Mass.

**THE ORIGINAL UNVULCANIZED PACKING**  
CALLED THE STANDARD.—As it is the Packing by which all others are compared.  
Accept no packing as JENKINS PACKING unless stamped with our "Trade Mark."  
71 John Street, N. Y.  
105 Milk Street, Boston.  
21 North 5th St., Phila.  
54 Dearborn St., Chicago.

**HARRISON CONVEYOR!**  
For Handling Grain, Coal, Sand, Clay, Tan Bark, Cinders, Ores, Seeds, &c.  
Send for Circulars. **BORDEN, SELLECK & CO.,** Sole Mfrs., Chicago, Ill.



**ICE-BOATS—THEIR CONSTRUCTION**  
and management. With working drawings, details, and directions in full. Four engravings showing mode of construction. Views of the two fastest ice-sailing boats used on the Hudson river in winter. By H. A. Horsfall, M.E. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 1. The same number also contains the rules and regulations for the formation of ice-boat clubs, the sailing and management of ice-boats. Price 10 cents.

**CONTRACTORS**  
WE MAKE THE LARGEST LINE OF ROAD GRADERS, SCRAPERS, PLOWING, AND RR CONSTRUCTION TOOLS IN THE WORLD.  
**WELL TOOLS**  
WE MANUFACTURE THE LARGEST LINE OF WELLBORING TOOLS IN THE WORLD.  
**NEW ERA**  
Railroad Builder, Wagon Road Grader, Wagon Loader, and Ditching Machine. It will place in an embankment 1000 cubic yards of earth in 10 hours at a cost of 1 1/2 to 2 1/2 cts. per yd.  
**CARPENTER ST. & CARROLL AVE.—CHICAGO ILL.**

## Scientific Book Catalogue

RECENTLY PUBLISHED.


Our new catalogue containing over 100 pages, including works on more than fifty different subjects. Will be mailed free to any address on application.

**MUNN & CO., Publishers Scientific American,**

361 Broadway, New York.

## SYRACUSE MALLEABLE IRON WORKS

Established 37 years, and at present the largest Elevator Works in the world. **OTIS BROTHERS & CO.,** General Offices, 38 Park Row, New York City, and branch offices in nearly every principal city on the globe. Elevators for Passengers and Freight. They are smooth-running, economical, and above all **SAFE.**



## COMPTOMETER

ALL ARITHMETICAL PROBLEMS

Solved rapidly and accurately by using the Comptometer. Saves 40 per cent. of time. Entire relief from mental strain. Adapted to all commercial and scientific computations. Send for circular.

**FELT & TARRANT MFG. CO.,** 52-56 Illinois St., Chicago.

**ELECTRO MOTOR. SIMPLE. HOW TO**  
make. By G. M. Hopkins.—Description of a small electro motor devised and constructed with a view to assisting amateurs to make a motor which might be driven with advantage by a current derived from a battery, and which would have sufficient power to operate a foot lathe or any machine requiring not over one man power, with 11 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 641. Price 10 cents. To be had at this office and from all newsdealers.

**COPPER TUBES**  
SHEET BRASS BRASS WIRE

## THE Scientific American

ESTABLISHED 1846.

The Most Popular Scientific Paper in the World.

Only \$3.00 a Year, including Postage. Weekly. 52 Numbers a Year.

This widely circulated and splendidly illustrated paper is published weekly. Every number contains sixteen pages of useful information and a large number of original engravings of new inventions and discoveries, representing Engineering Works, Steam Machinery, New Inventions. Novelties in Mechanics, Manufactures, Chemistry, Electricity, Telegraphy, Photography, Architecture, Agriculture, Horticulture, Natural History, etc. Complete List of Patents each week.

**Terms of Subscription.**—One copy of the SCIENTIFIC AMERICAN will be sent for one year—52 numbers—postage prepaid, to any subscriber in the United States, Canada or Mexico, on receipt of three dollars by the publishers: six months, \$1.50; three months, \$1.00.

**Clubs.**—Special rates for several names, and to Post Masters. Write for particulars.

The safest way to remit is by Postal Order, Draft, or Express Money Order. Money carefully placed inside of envelopes, securely sealed, and correctly addressed, seldom goes astray, but is at the sender's risk. Address all letters and make all orders, drafts, etc., payable to

**MUNN & CO.,**  
361 Broadway, New York.

## THE Scientific American Supplement.

This is a separate and distinct publication from THE SCIENTIFIC AMERICAN, but is uniform therewith in size, every number containing sixteen large pages full of engravings, many of which are taken from foreign papers, and accompanied with translated descriptions. THE SCIENTIFIC AMERICAN SUPPLEMENT is published weekly, and includes a very wide range of contents. It presents the most recent papers by eminent writers in all the principal departments of Science and the Useful Arts, embracing Biology, Geology, Mineralogy, Natural History, Geography, Archeology, Astronomy, Chemistry, Electricity, Light, Heat, Mechanical Engineering, Steam and Railway Engineering, Mining, Ship Building, Marine Engineering, Photography, Technology, Manufacturing Industries, Sanitary Engineering, Agriculture, Horticulture, Domestic Economy, Biography, Medicine, etc. A vast amount of fresh and valuable information obtainable in no other publication.

The most important Engineering Works, Mechanisms, and Manufactures at home and abroad are illustrated and described in the SUPPLEMENT.

Price for the SUPPLEMENT for the United States and Canada, \$5.00 a year, or one copy of the SCIENTIFIC AMERICAN and one copy of the SUPPLEMENT, both mailed for one year for \$7.00. Single copies 10 cents. Address and remit by postal order, express money order, or check.

**MUNN & CO., 361 Broadway, N. Y.,**  
Publishers SCIENTIFIC AMERICAN.

## Building Edition.

THE SCIENTIFIC AMERICAN ARCHITECTS' AND BUILDERS' EDITION is issued monthly. \$2.50 a year. Single copies, 25 cents. Forty large quarto pages, equal to about two hundred ordinary book pages, forming a large and splendid Magazine of Architecture, richly adorned with elegant plates in color, and with other fine engravings; illustrating the most interesting examples of modern Architectural Construction and allied subjects.

A special feature is the presentation in each number of a variety of the latest and best plans for private residences, city and country, including those of very moderate cost as well as the more expensive. Drawings in perspective and in color are given, together with full Plans, Specifications, Sheets of Details, Estimates, etc.

The elegance and cheapness of this magnificent work have won for it the Largest Circulation of any Architectural publication in the world. Sold by all newsdealers. \$2.50 a year. Remit to

**MUNN & CO., Publishers,**

361 Broadway, New York.

## PRINTING INKS.

THE "Scientific American" is printed with CHAS. T. JENU JOHNSON & CO.'S INK. Tenth and Lombard Sts., Phila., and 47 Rose St., opp. Duane St., N. Y.